


STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐**APPLICATION FOR PERMIT TO DRILL**

2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>				1. WELL NAME and NUMBER Bonanza 1023-15I2AS		
4. TYPE OF WELL Gas Well Coalbed Methane Well: NO				3. FIELD OR WILDCAT NATURAL BUTTES		
6. NAME OF OPERATOR KERR-MCGEE OIL & GAS ONSHORE, L.P.				5. UNIT or COMMUNITIZATION AGREEMENT NAME		
8. ADDRESS OF OPERATOR P.O. Box 173779, Denver, CO, 80217				7. OPERATOR PHONE 720 929-6587		
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) UTU 38427		11. MINERAL OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>		9. OPERATOR E-MAIL mary.mondragon@anadarko.com		
13. NAME OF SURFACE OWNER (if box 12 = 'fee')				12. SURFACE OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>		
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')				14. SURFACE OWNER PHONE (if box 12 = 'fee')		
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')				16. SURFACE OWNER E-MAIL (if box 12 = 'fee')		
18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input checked="" type="checkbox"/> (Submit Commingling Application) NO <input type="checkbox"/>		19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>				
20. LOCATION OF WELL	FOOTAGES	QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN
LOCATION AT SURFACE	2199 FSL 339 FEL	NESE	15	10.0 S	23.0 E	S
Top of Uppermost Producing Zone	2425 FSL 700 FEL	NESE	15	10.0 S	23.0 E	S
At Total Depth	2425 FSL 700 FEL	NESE	15	10.0 S	23.0 E	S
21. COUNTY UINTAH		22. DISTANCE TO NEAREST LEASE LINE (Feet) 700		23. NUMBER OF ACRES IN DRILLING UNIT 640		
		25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 445		26. PROPOSED DEPTH MD: 7951 TVD: 7900		
27. ELEVATION - GROUND LEVEL 5604		28. BOND NUMBER WYB000291		29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE Permit #43-8496		

ATTACHMENTS**VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES**

<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)	<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)	<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP
NAME Danielle Piernot	TITLE Regulatory Analyst
SIGNATURE	PHONE 720 929-6156
API NUMBER ASSIGNED 43047507420000	DATE 09/11/2009
APPROVAL	EMAIL danielle.piernot@anadarko.com
 Permit Manager	

Proposed Hole, Casing, and Cement						
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Prod	7.875	4.5	0	7951		
Pipe	Grade	Length	Weight			
	Grade I-80 Buttreass	7951	11.6			

Proposed Hole, Casing, and Cement						
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Surf	12.25	9.625	0	2030		
Pipe	Grade	Length	Weight			
	Grade J-55 LT&C	2030	36.0			

, APIWellNo:43047507420000,

Well location, BONANZA #1023-1512AS, located as shown in the NE 1/4 SE 1/4 of Section 15, T10S, R23E, S.L.B.&M., Uintah County, Utah.

BENCH MARK 58 EAM (1965) LOCATED IN THE NE 1/4 OF SECTION 30, T9S, R23E, S.L.B.&M. TAKEN FROM THE RED WASH SE, QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5132 FEET.

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.

BONANZA #1023-15/2AS
 Elev. Ungraded Ground = 5604'

LINE TABLE

LINE	BEARING	LENGTH
L1	S36°20'56"W	545.31'
L2	N57°58'21"W	436.06'

Boundaries and Distances:

- Top Left: N89°58'39"E - 2652.42' (Meas.)
- Top Right: S89°29'57"E - 2634.34' (Meas.)
- Right: S00°02'03"E - 2638.56' (Meas.)
- Bottom Right: 2645.94' (G.L.O.)
- Bottom: 3802.26' (G.L.O.)
- Bottom Left: S89°55'35"W 1585.54' (Meas.)
- Left: N00°20'00"E - 2612.55' (Meas.)
- Left: N00°15'20"W - 2639.18' (Meas.)

Monuments and Features:

- Top Left: 1995 Alum. Cap, 0.3' Above 2.5' High Pile of Stones
- Top Right: 1995 Alum. Cap, 0.4' Above 2.0' High Pile of Stones
- Top Right: 1995 Alum. Cap, 0.4' High, Pile of Stones
- Right: 1994 Alum. Cap, 0.3' High, Pile of Stones, Steel Post
- Bottom Right: 177°57' (G.L.O.)
- Bottom Right: 339' (Comp)
- Bottom Right: 2425' (G.L.O.)
- Bottom Right: 2199' (Comp)
- Bottom Right: 87°07' (G.L.O.)
- Bottom Left: 1995 Alum. Cap, 0.6' High, Pile of Stones
- Bottom Left: 1995 Alum. Cap, 1.0' High, Pile of Stones, Steel Post
- Bottom Left: W.C. 1995 Alum. Cap, 2.0' High, Pile of Stones
- Center: 15
- Center: Bottom Hole
- Center: 700'
- Center: L1
- Center: L2



THIS IS TO CERTIFY THAT THE ABOVE PLAN WAS PREPARED FROM
FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY
SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE
BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
REGISTRATION NO. 161319
STATE OF UTAH

85 SOUTH 200 EAST - VERNAL, UTAH 84078

LEGEND:

- └ = 90° SYMBOL
● = PROPOSED WELL HEAD.
▲ = SECTION CORNERS LOCATED.




NAD 83 (TARGET BOTTOM HOLE)	NAD 83 (SURFACE LOCATION)
LATITUDE = 39°56'54.28" (39.948411)	LATITUDE = 39°56'52.00" (39.947778)
LONGITUDE = 109°18'22.08" (109.306133)	LONGITUDE = 109°18'17.33" (109.304814)
NAD 27 (TARGET BOTTOM HOLE)	NAD 27 (SURFACE LOCATION)
LATITUDE = 39°56'54.40" (39.948444)	LATITUDE = 39°56'52.12" (39.947811)
LONGITUDE = 109°18'19.65" (109.305458)	LONGITUDE = 109°18'14.90" (109.304139)

SCALE 1" = 1000'		DATE SURVEYED: 02-23-09	DATE DRAWN: 02-25-09
PARTY D.K. D.C. S.P.		REFERENCES G.L.O. PLAT	
WEATHER COLD		FILE Kerr-McGee Oil & Gas Onshore LP	

'APIWellNo:43047507420000'



Well Name: P_BONANZA 1023-15I2AS
 Surface Location: UINTAH_BONANZA 1023-15I PAD
 NAD 1927 (NADCON CONUS)US State Plane 1927 (Exact solution)
 UTAH CENTRAL ZONE - 27
 Ground Elevation: 5603.0
 Northing 595592.26 Easting 2615560.34 Latitude 39.947811°N Longitude 109.304139°W



SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0
2	2050.0	0.00	0.00	2050.0	0.0	0.0	0.00	0.00	0.0
3	2925.0	17.50	301.94	2911.5	70.2	-112.5	2.00	301.94	132.6
4	3345.3	17.50	301.94	3312.3	137.0	-219.8	0.00	0.00	259.0
5	4512.0	0.00	0.00	4461.0	230.6	-369.8	1.50	180.00	435.8
6	7951.1	0.00	0.00	7900.0	230.6	-369.8	0.00	0.00	435.8



Azimuths to True North
 Magnetic North: 11.25°

Magnetic Field
 Strength: 52565.8snT
 Dip Angle: 65.93°
 Date: 4/13/2009
 Model: IGRF200510

ROCKIES - PLANNING

UTAH CENTRAL ZONE - 27

UINTAH_BONANZA 1023-15I PAD

P_BONANZA 1023-15I2AS

P_BONANZA 1023-15I2AS

Plan: Plan #1 04-13-09 ZJRA6

Standard Planning Report - Geographic

13 April, 2009

APC

Planning Report - Geographic

Database:	apc_edmp	Local Co-ordinate Reference:	Well P_BONANZA 1023-15I2AS
Company:	ROCKIES - PLANNING	TVD Reference:	WELL @ 5603.0ft (Original Well Elev)
Project:	UTAH CENTRAL ZONE - 27	MD Reference:	WELL @ 5603.0ft (Original Well Elev)
Site:	UINTAH_BONANZA 1023-15I PAD	North Reference:	True
Well:	P_BONANZA 1023-15I2AS	Survey Calculation Method:	Minimum Curvature
Wellbore:	P_BONANZA 1023-15I2AS		
Design:	Plan #1 04-13-09 ZJRA6		

Project	UTAH CENTRAL ZONE - 27		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	Utah Central 4302		

Site		UINTAH_BONANZA 1023-15I PAD				
Site Position:		Northing:	595,601.23ft	Latitude:	39.947833°N	
From:	Lat/Long	Easting:	2,615,599.10ft	Longitude:	109.304000°W	
Position Uncertainty:		0.0 ft	Slot Radius:	"	Grid Convergence:	1.41 °

Well	P_BONANZA 1023-15I2AS					
Well Position	+N/-S	0.0 ft	Northing:	595,592.26 ft	Latitude:	39.947811°N
	+E/-W	0.0 ft	Easting:	2,615,560.34 ft	Longitude:	109.304139°W
Position Uncertainty		0.0 ft	Wellhead Elevation:	ft	Ground Level:	5,603.0ft

Wellbore	P_BONANZA 1023-15I2AS				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF200510	4/13/2009	11.25	65.93	52,566

Design	Plan #1 04-13-09 ZJRA6			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)
	7,900.0	0.0	0.0	301.94

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
2,050.0	0.00	0.00	2,050.0	0.0	0.0	0.00	0.00	0.00	0.00	
2,925.0	17.50	301.94	2,911.5	70.2	-112.5	2.00	2.00	0.00	301.94	
3,345.3	17.50	301.94	3,312.3	137.0	-219.8	0.00	0.00	0.00	0.00	
4,512.0	0.00	0.00	4,461.0	230.6	-369.8	1.50	-1.50	0.00	180.00	
7,951.1	0.00	0.00	7,900.0	230.6	-369.8	0.00	0.00	0.00	0.00	PBHL_BONANZA 1

APC

Planning Report - Geographic

Database:	apc_edmp	Local Co-ordinate Reference:	Well P_BONANZA 1023-15I2AS
Company:	ROCKIES - PLANNING	TVD Reference:	WELL @ 5603.0ft (Original Well Elev)
Project:	UTAH CENTRAL ZONE - 27	MD Reference:	WELL @ 5603.0ft (Original Well Elev)
Site:	UINTAH_BONANZA 1023-15I PAD	North Reference:	True
Well:	P_BONANZA 1023-15I2AS	Survey Calculation Method:	Minimum Curvature
Wellbore:	P_BONANZA 1023-15I2AS		
Design:	Plan #1 04-13-09 ZJRA6		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (ft)	Map Easting (ft)	Latitude	Longitude
0.0	0.00	0.00	0.0	0.0	0.0	595,592.26	2,615,560.34	39.947811°N	109.304139°W
970.0	0.00	0.00	970.0	0.0	0.0	595,592.26	2,615,560.34	39.947811°N	109.304139°W
Green River									
1,900.0	0.00	0.00	1,900.0	0.0	0.0	595,592.26	2,615,560.34	39.947811°N	109.304139°W
Surface Casing									
2,050.0	0.00	0.00	2,050.0	0.0	0.0	595,592.26	2,615,560.34	39.947811°N	109.304139°W
2,925.0	17.50	301.94	2,911.5	70.2	-112.5	595,659.63	2,615,446.14	39.948004°N	109.304540°W
3,345.3	17.50	301.94	3,312.3	137.0	-219.8	595,723.85	2,615,337.27	39.948187°N	109.304923°W
4,020.7	7.37	301.94	3,971.0	213.9	-343.0	595,797.65	2,615,212.18	39.948398°N	109.305362°W
Wasatch									
4,512.0	0.00	0.00	4,461.0	230.6	-369.8	595,813.68	2,615,185.00	39.948444°N	109.305458°W
7,381.1	0.00	0.00	7,330.0	230.6	-369.8	595,813.68	2,615,185.00	39.948444°N	109.305458°W
Mesa Verde									
7,951.1	0.00	0.00	7,900.0	230.6	-369.8	595,813.68	2,615,185.00	39.948444°N	109.305458°W

Targets									
Target Name									
- hit/miss target	Dip Angle	Dip Dir.	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
- Shape	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(ft)		
PBHL_BONANZA 102	0.00	0.00	7,900.0	230.6	-369.8	595,813.68	2,615,185.00	39.948444°N	109.305458°W
- plan hits target center									
- Point									

Casing Points					
Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (")	Hole Diameter (")	
1,900.0	1,900.0	Surface Casing	9-5/8	12-1/4	

Formations					
Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)
4,020.7	3,971.0	Wasatch		0.00	
970.0	970.0	Green River		0.00	
7,381.1	7,330.0	Mesa Verde		0.00	

Bonanza 1023-15I2AS

Pad: Bonanza 1023-15I
Surface: 2,199' FSL 339' FEL (NE/4SE/4)
BHL: 2,425' FSL 700' FEL (NE/4SE/4)
Sec. 15 T10S R23E

Uintah, Utah
Mineral Lease: UTU 38427

ONSHORE ORDER NO. 1

DRILLING PROGRAM

**1. – 2. Estimated Tops of Important Geologic Markers:
Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:**

<u>Formation</u>	<u>Depth</u>	<u>Resource</u>
Uinta	0 – Surface	
Green River	970'	
Birds Nest	1,329'	Water
Mahogany	1,828'	Water
Wasatch	3,971'	Gas
Mesaverde	5,743'	Gas
MVU2	6,729'	Gas
MVL1	7,330'	Gas
TVD	7,900'	
TD	7,951'	

3. Pressure Control Equipment (Schematic Attached)

Please refer to the attached Drilling Program.

4. Proposed Casing & Cementing Program:

Please refer to the attached Drilling Program.

5. Drilling Fluids Program:

Please refer to the attached Drilling Program.

6. Evaluation Program:

Please refer to the attached Drilling Program.

7. Abnormal Conditions:

Maximum anticipated bottomhole pressure calculated at 7,900' TVD, approximately equals 4,706 psi (calculated at 0.59 psi/foot).

Maximum anticipated surface pressure equals approximately 2,938 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

8. Anticipated Starting Dates:

Drilling is planned to commence immediately upon approval of this application.

9. Variances:

Please refer to the attached Drilling Program.

Onshore Order #2 – Air Drilling Variance

Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2

- *Blowout Prevention Equipment (BOPE) requirements;*
- *Mud program requirements; and*
- *Special drilling operation (surface equipment placement) requirements associated with air drilling.*

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

Background

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In

some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 12-1/4 inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 12-1/4 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 9-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

Variance for Mud Material Requirements

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet

from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

Variance for FIT Requirements

KMG also respectfully requests a variance to Onshore Order 2, Section III, Part Bi, for the pressure integrity test (PIT, also known as a formation integrity test (FIT)). The air rig operation utilizes a 5M BOPE when drilling. This well is not an exploratory well and is being drilled in an area where the formation integrity is well known. Additionally, when an FIT is run with the mud weight as required, the casing shoe frequently breaks down and causes subsequent lost circulation when drilling the entire depth of the well.

Conclusion

The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.

10. Other Information:

Please refer to the attached Drilling Program.

COMPANY NAME	KERR-McGEE OIL & GAS ONSHORE LP					DATE	September 11, 2009	
WELL NAME	Bonanza 1023-15I2AS					TD	7,900'	7,951' MD
FIELD	Natural Buttes		COUNTY	Uintah	STATE	Utah	FINISHED ELEVATION	5,603'
SURFACE LOCATION	NE/4 SE/4	2,199' FSL	339' FEL	Sec 15	T 10S	R 23E		
	Latitude: 39.947778		Longitude: -109.304814		NAD 83			
BTM HOLE LOCATION	NE/4 SE/4	2,425' FSL	700' FEL	Sec 15	T 10S	R 23E		
	Latitude: 39.948411		Longitude: -109.306133		NAD 83			
OBJECTIVE ZONE(S)	Wasatch/Mesaverde							
ADDITIONAL INFO	Regulatory Agencies: BLM (Minerals), BLM (Surface), UDOGM Tri-County Health Dept.							

Bonanza 1023-15I2AS Drilling Program-Directional well-updated 081209.xls



KERR-McGEE OIL & GAS ONSHORE LP

DRILLING PROGRAM

CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'						
						3,520	2,020	453,000
SURFACE	9-5/8"	0 to 2,030	36.00	J-55	LTC	1.16	2.13	7.89
						7,780	6,350	278,000
PRODUCTION	4-1/2"	0 to 7,951	11.60	I-80	BTC	2.57	1.33	3.45

1) Max Anticipated Surf. Press.(MASP) (Surface Casing) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

2) MASP (Prod Casing) = Pore Pressure at TD - (0.22 psi/ft-partial evac gradient x TD)

(Burst Assumptions: TD = 11.6 ppg)

0.22 psi/ft = gradient for partially evac wellbore

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

MASP 2,938 psi

3) Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

(Burst Assumptions: TD = 11.6 ppg)

0.59 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

MABHP 4,706 psi

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	500'	Premium cmt + 2% CaCl	215	60%	15.60	1.18
			+ 0.25 pps flocele				
Option 1	TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	380	0%	15.60	1.18
			+ 2% CaCl + 0.25 pps flocele				
			Premium cmt + 2% CaCl				
SURFACE		NOTE: If well will circulate water to surface, option 2 will be utilized					
Option 2	LEAD	1,530'	65/35 Poz + 6% Gel + 10 pps gilsonite	360	35%	12.60	1.81
			+ 0.25 pps Flocele + 3% salt BWOW				
	TAIL	500'	Premium cmt + 2% CaCl	180	35%	15.60	1.18
			+ 0.25 pps flocele				
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
PRODUCTION	LEAD	3,471'	Premium Lite II + 3% KCl + 0.25 pps	330	40%	11.00	3.38
			celloflake + 5 pps gilsonite + 10% gel				
			+ 0.5% extender				
	TAIL	4,480'	50/50 Poz/G + 10% salt + 2% gel	1,100	40%	14.30	1.31
			+ 0.1% R-3				

*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. No centralizers will be used.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

John Huycke / Emile Goodwin

DATE:

DRILLING SUPERINTENDENT:

John Merkel / Lovel Young

DATE:

EXHIBIT A
Bonanza 1023-15I2AS


NAD 83 (EXIST. SWD #3)
LATITUDE = 39°56'51.81" (39.947725)
LONGITUDE = 109°18'18.33" (109.305092)
NAD 27 (EXIST. SWD #3)
LATITUDE = 39°56'51.93" (39.947758)
LONGITUDE = 109°18'15.90" (109.304417)

Kerr-McGee Oil & Gas Onshore LP






TYPICAL CROSS SECTIONS FOR

BONANZA #1023-15H4CS, #1023-15I2AS, #1023-15I4BS & #1023-15P1BS
SECTION 15, T10S, R23E, S.L.B.&M.
NE 1/4 SE 1/4

FIGURE #2



DATE: 02-25-09
Drawn By: S.P.



NOTE:
Topsoil should not be
Stripped Below Finished
Grade on Substructure Area.

APPROXIMATE ACREAGES
WELL SITE DISTURBANCE = ± 4.405 ACRES
ACCESS ROAD DISTURBANCE = ± 0.150 ACRES
PIPELINE DISTURBANCE = ± 0.084 ACRES
TOTAL = ± 4.639 ACRES

* NOTE:
FILL QUANTITY INCLUDES
5% FOR COMPACTION

APPROXIMATE YARDAGES

(6") Topsoil Stripping = 3,120 Cu. Yds.
Remaining Location = 20,040 Cu. Yds.
TOTAL CUT = 23,160 CU.YDS.
FILL = 12,870 CU.YDS.

EXCESS MATERIAL = 10,290 Cu. Yds.
Topsoil & Pit Backfill = 6,840 Cu. Yds.
(1/2 Pit Vol.)
EXCESS UNBALANCE = 3,450 Cu. Yds.
(After Interim Rehabilitation)



UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

Kerr-McGee Oil & Gas Onshore LP

TYPICAL RIG LAYOUT FOR


BONANZA #1023-15H4CS, #1023-15I2AS, #1023-15I4BS & #1023-15P1BS
SECTION 15, T10S, R23E, S.L.B.&M.
NE 1/4 SE 1/4

FIGURE #3



SCALE: 1" = 50'
DATE: 02-25-09
Drawn By: S.P.


NOTE:
Flare Pit is to be
located a min. of 100'
from the Well Head.



U E L S
Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC MAP		05 MONTH	24 DAY	06 YEAR
SCALE: 1:100,000	DRAWN BY: C.P.	REV: J.H. 02-24-09		

A
TOPO



LEGEND:

— EXISTING ROAD
- - - PROPOSED ACCESS ROAD



Kerr-McGee Oil & Gas Onshore LP
BONANZA #1023-15H4CS, #1023-15I2AS,
#1023-15I4BS & #1023-15P1BS
SECTION 15, T10S, R23E, S.L.B.&M.
NE 1/4 SE 1/4




Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

05 24 06
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.P. REV: J.H. 02-24-09





LEGEND:

- | | |
|-------------------|-------------------------|
| ○ DISPOSAL WELLS | ○ WATER WELLS |
| ● PRODUCING WELLS | ● ABANDONED WELLS |
| ● SHUT IN WELLS | ● TEMPORARILY ABANDONED |



Kerr-McGee Oil & Gas Onshore LP
BONANZA #1023-15H4CS, #1023-15I2AS,
#1023-15I4BS & #1023-15P1BS
SECTION 15, T10S, R23E, S.L.B.&M.
NE 1/4 SE 1/4




Utah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

05 24 06
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.P. REV: J.H. 02-24-09





APPROXIMATE TOTAL PIPELINE DISTANCE = 123' +/-

LEGEND:

- PROPOSED ACCESS ROAD
- EXISTING PIPELINE
- PROPOSED PIPELINE



Kerr-McGee Oil & Gas Onshore LP
BONANZA #1023-15H4CS, #1023-15I2AS,
#1023-15I4BS & #1023-15P1BS
SECTION 15, T10S, R23E, S.L.B.&M.
NE 1/4 SE 1/4



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

05 24 06
 MONTH DAY YEAR

SCALE: 1" = 1000' DRAWN BY: C.P. REV: J.H. 02-24-09



Kerr-McGee Oil & Gas Onshore LP

**BONANZA #1023-15H4CS, #1023-15I2AS,
#1023-15I4BS & #1023-15P1BS**

LOCATED IN UINTAH COUNTY, UTAH
SECTION 15, T10S, R23E, S.L.B.&M.



PHOTO: VIEW OF LOCATION STAKES

CAMERA ANGLE: NORTHWESTERLY



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: NORTHWESTERLY



- Since 1964 -

UELS Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

LOCATION PHOTOS

05 24 06
MONTH DAY YEAR

PHOTO

TAKEN BY: D.K.

DRAWN BY: C.P.

REV: J.H. 02-24-09

Kerr-McGee Oil & Gas Onshore LP

BONANZA #1023-15H4CS, #1023-15I2AS,
#1023-15I4BS & #1023-15P1BS

PIPELINE ALIGNMENT

LOCATED IN UINTAH COUNTY, UTAH

SECTION 15, T10S, R23E, S.L.B.&M.



PHOTO: VIEW FROM TIE-IN POINT

CAMERA ANGLE: NORTHWESTERLY



PHOTO: VIEW OF PIPELINE ALIGNMENT

CAMERA ANGLE: NORTHWESTERLY



- Since 1964 -

UELS Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

PIPELINE PHOTOS

05 24 06
MONTH DAY YEAR

PHOTO

TAKEN BY: D.K.

DRAWN BY: C.P.

REV: J.H. 02-24-09

**Kerr-McGee Oil & Gas Onshore LP
BONANZA #1023-15H4CS, #1023-15I2AS,
#1023-15I4BS & #1023-15P1BS
SECTION 15, T10S, R23E, S.L.B.&M.**

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 0.3 MILES ON THE SEEP RIDGE ROAD TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 12.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 1.7 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 1.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN RIGHT AND PROCEED IN A SOUTHEASTERLY DIRECTION APPROXIMATELY 0.5 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 3.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN RIGHT AND PROCEED IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 0.7 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN LEFT AND PROCEED IN A SOUTHEASTERLY, THEN SOUTHERLY DIRECTION APPROXIMATELY 1.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A SOUTHERLY, THEN SOUTHWESTERLY, THEN SOUTHERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 3.4 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHEAST; TURN LEFT AND PROCEED IN A NORTHEASTERLY, THEN EASTERLY DIRECTION APPROXIMATELY 4.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A SOUTHERLY, THEN SOUTHWESTERLY DIRECTION APPROXIMATELY 2.3 MILES TO THE BEGINNING OF THE PROPOSED ACCESS TO THE NORTH; FOLLOW ROAD FLAGS IN A NORTHERLY DIRECTION APPROXIMATELY 225' TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 64.2 MILES.

Bonanza 1023-15H4CS

Surface: 2,204' FSL 319' FEL (NE/4SE/4)

BHL: 2,450' FNL 535' FEL (SE/4NE/4)

Bonanza 1023-15I2AS

Surface: 2,199' FSL 339' FEL (NE/4SE/4)

BHL: 2,425' FSL 700' FEL (NE/4SE/4)

Bonanza 1023-15I4BS

Surface: 2,194' FSL 359' FEL (NE/4SE/4)

BHL: 1,915' FSL 620' FEL (NE/4SE/4)

Bonanza 1023-15P1BS

Surface: 2,208' FSL 300' FEL (NE/4SE/4)

BHL: 1,080' FSL 615' FEL (SE/4SE/4)

Pad: Bonanza 1023-15I

Sec. 15 T10S R23E

Uintah, Utah

Mineral Lease: UTU 38427

ONSHORE ORDER NO. 1

***MULTI-POINT SURFACE USE & OPERATIONS PLAN
SUBMITTED WITH SITE-SPECIFIC INFORMATION***

This Application for Permit to Drill (APD) is filed under the Notice of Staking (NOS) process as stated in Onshore Order No. 1 (OSO #1) and supporting Bureau of Land Management (BLM) documents. An NOS was submitted on May 7, 2009 showing the surface locations in NE/4 SE/4 of Section 15 T10S R23E.

This Surface Use Plan of Operations (SUPO) or 13-point plan provides the site-specific information for the above-referenced wells. This information is to be incorporated by reference into the Master Development Plan (MDP) for Kerr-McGee Oil & Gas Onshore LP (Kerr-McGee). The MDP is available upon request from the BLM-Vernal Field Office.

An on-site meeting was held on May 27, 2009. Present were:

- Verlyn Pindell, Dave Gordon, Scott Ackerman – BLM;
- Kolby Kay – 609 Consulting, LLC;
- Tony Kazeck, Raleen White and Hal Blanchard – Kerr-McGee.

Directional Drilling:

In accordance with Utah Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling, this well will be directionally drilled in order to access portions of our lease which are otherwise inaccessible due to topography.

A. Existing Roads:

- A) Refer to Topo Map A for directions to the location.
- B) Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

B. Planned Access Roads:

See MDP for additional details on road construction.

Approximately $\pm 230'$ (± 0.04 mile) of new access road is proposed. Please refer to the attached Topo Map B. No pipelines will be crossed with the new construction.

Existence of pipelines; maximum grade; turnouts; major cut and fills, culverts, or bridges; gates, cattle guards, fence cuts, or modifications to existing facilities were determined at the on-site and are typically shown on the attached Exhibits and Topo maps.

C. Location of Existing Wells Within a 1-Mile Radius:

Please refer to Topo Map C.

D. Location of Existing and Proposed Facilities:

See MDP for additional details on Existing and Proposed Facilities.

This pad will expand the existing pad for the SWD #3, which is a Dry Hole according to Utah Division of Oil, Gas and Mining (UDOGM) records.

The following guidelines will apply if the well is productive.

Approximately $\pm 123'$ (± 0.02 miles) of pipeline is proposed. Refer to Topo D for the existing pipeline. Pipeline segments will be welded or zaplocked together on disturbed areas in or near the location, whenever possible, and dragged into place.

Per the onsite meeting, the following items were requested/discussed:

- Install a 30 mil pit liner and felt
- Clean out existing pond
- 4" of topsoil
- Keep spoils out of drainage at corners 1 and 2

E. Location and Type of Water Supply:

See MDP for additional details on Location and Type of Water Supply.

Water for drilling purposes will be obtained from one of the following sources:

- Dalbo Inc.'s underground well located in Ouray, Utah, Sec. 32 T4S R3E, Water User Claim number 43-8496, application number 53617.
- Price Water Pumping Inc. Green River and White River, various sources, Water Right Number 49-1659, application number: a35745.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

F. Source of Construction Materials:

See MDP for additional details on Source of Construction Materials.

G. Methods of Handling Waste Materials:

See MDP for additional details on Methods of Handling Waste Materials.

Any produced water from the proposed well will be contained in a water tank and will then be hauled by truck to one of the pre-approved disposal sites:

RNI in Sec. 5 T9S R22E
NBU #159 in Sec. 35 T9S R21E
Ace Oilfield in Sec. 2 T6S R20E
MC&MC in Sec. 12 T6S R19E
Pipeline Facility in Sec. 36 T9S R20E
Goat Pasture Evaporation Pond in SW/4 Sec. 16 T10S R22E
Bonanza Evaporation Pond in Sec. 2 T10S R23E

H. Ancillary Facilities:

See MDP for additional details on Ancillary Facilities.

None are anticipated.

I. Well Site Layout: (See Location Layout Diagram)

See MDP for additional details on Well Site Layout.

All pits will be fenced according to the following minimum standards:

- Net wire (39-inch) will be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.
- The net wire shall be no more than two inches above the ground. The barbed wire shall be three inches over the net wire. Total height of the fence shall be at least 42 inches.
- Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
- Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.
- All wire shall be stretched, by using a stretching device, before it is attached to corner posts.

J. Plans for Reclamation of the Surface:

See MDP for additional details on Plans for Reclamation of the Surface.

K. Surface/Mineral Ownership:

United States of America
Bureau of Land Management
170 South 500 East
Vernal, UT 84078
(435)781-4400

L. Other Information:

See MDP for additional details on Other Information.

Stipulations:

- Oil/Tar sand lease stipulation:
No surface occupancy from May 15 through July 20.

M. Lessee's or Operators' Representative & Certification:

Kathy Schneebeck Dulnoan
Regulatory Analyst
Kerr-McGee Oil & Gas Onshore LP
PO Box 173779
Denver, CO 80217-3779
(720) 929-6007

Tommy Thompson
General Manager, Drilling
Kerr-McGee Oil & Gas Onshore LP
PO Box 173779
Denver, CO 80217-3779
(720) 929-6724

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Bureau of Land Management Nationwide Bond WYB000291.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that I have full knowledge of the State and Federal laws applicable to this operation; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.


Kathy Schneebeck Dulnoan

September 10, 2009
Date



Kerr-McGee Oil & Gas Onshore LP
P.O. Box 173779
Denver, CO 80217-3779

July 8, 2009

Ms. Diana Mason
Division of Oil, Gas and Mining
P.O. Box 145801
Salt Lake City, UT 84114-6100

Re: Exception Location R649-3-3 and Directional Drilling R649-3-11
Bonanza 1023-1512AS
T10S- R23E
Section 15: NESE
2199' FSL, 339' FEL (surface)
2425' FSL, 700' FEL (bottom hole)
Uintah County, Utah

Dear Ms. Mason:

Pursuant to the filing of Kerr-McGee Oil & Gas Onshore LP's (Kerr-McGee) Application for Permit to Drill regarding the above referenced well, we are hereby submitting this letter in accordance with Oil & Gas Conservation Rule R649-3-3 and Rule R649-3-11 pertaining to the Exception to Location and Sitting of Wells.

- Kerr-McGee's Bonanza 1023-1512AS is located within the area covered by Docket No. 2008-011 authorizing the equivalent of an approximate 10-acre well density pattern, and requiring approval for wells drilled at an exception location and wells drilled directionally in accordance with the referenced rules.
- Kerr-McGee is permitting this well at this location for geological reasons. Locating the well at the surface location and directionally drilling from this location, Kerr-McGee will be able to minimize surface disturbance.

Therefore, based on the above stated information Kerr-McGee Oil & Gas Onshore LP requests the permit be granted pursuant to Rule R649-3 and Rule R649-3-11.

Sincerely,

KERR-MCGEE OIL & GAS ONSHORE LP

A handwritten signature in blue ink that reads 'Jessy Pink'.

Jessy Pink
Landman

CULTURAL RESOURCE INVENTORY OF
KERR-MCGEE OIL & GAS ONSHORE LP'S PROPOSED
WELL LOCATIONS: BONANZA #1023-10N DIRECTIONAL PAD,
BONANZA #1023-10N3DS, BONANZA #1023-15I DIRECTIONAL PAD,
BONANZA #1023-15H4CS, BONANZA #1023-15I2AS,
BONANZA #1023-15I4BS, AND BONANZA #1023-15P1BS
(T10S, R23E, SECTIONS 10 AND 15)
UINTAH COUNTY, UTAH

By:

Patricia Stavish

Prepared For:

Bureau of Land Management
Vernal Field Office

Prepared Under Contract With:

Kerr-McGee Oil & Gas Onshore LP
1368 South 1200 East
Vernal, Utah 84078

Prepared By:

Montgomery Archaeological Consultants, Inc.
P.O. Box 219
Moab, Utah 84532

MOAC Report No. 09-046

May 11, 2009

United States Department of Interior (FLPMA)
Permit No. 09-UT-60122

State of Utah Antiquities Project (Survey)
Permit No. U-09-MQ-0230b

IPC #09-67

Paleontological Reconnaissance Survey Report

**Survey of Kerr McGee's Proposed Multi-Well Pad, Access Road,
and Pipeline for "Bonanza #1023-15H4CS, I2AS, I4BS,
& P1BS" (Sec. 15, T 10 S, R 23 E)**

Asphalt Wash
Topographic Quadrangle
Uintah County, Utah

April 23, 2009

Prepared by Stephen D. Sandau
Paleontologist for
Intermountain Paleo-Consulting
P. O. Box 1125
Vernal, Utah 84078



Grasslands Consulting, Inc.

4800 Happy Canyon Road, Suite 110, Denver, CO 80237

(303) 759-5377 Office (303) 759-5324 Fax

SPECIAL STATUS PLANT AND WILDLIFE SPECIES REPORT

Report #: GCI#17

Operator: Kerr-McGee Oil & Gas Onshore LP

Well: Bonanza 1023-15I pad (Bores: Bonanza 1023-15H4CS, Bonanza 1023-15I2AS, Bonanza 1023-15I4BS, and Bonanza 1023-15P1BS).

Pipeline: Proposed pipeline from southwest corner of well pad to intersection with existing pipeline south of location.

Access Road: Proposed access road from existing access road east of location.

Location: Section 15, Township 10 South, Range 23 East; Uintah County, Utah.

Survey-Species: Uinta Basin Hookless Cactus (*Sclerocactus wetlandicus*) and nesting raptors.

Date: 05/05/2009

Observer(s): Grasslands Consulting, Inc. Biologists: Nick Hall, Dan Hamilton, and Jonathan Sexauer. Technician: Chad Johnson.

Weather: Partly cloudy, 60-75°F, 5-10mph winds.

API Number: 4304750742

Well Name: Bonanza 1023-15I2AS




Township 10.0 S Range 23.0 E Section 15

Meridian: SLBM

Operator: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Map Prepared:

Map Produced by Diana Mason



WORKSHEET

APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 9/11/2009

API NO. ASSIGNED: 43047507420000

WELL NAME: Bonanza 1023-15I2AS

OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P. (N2995)

PHONE NUMBER: 720 929-6156

CONTACT: Danielle Piernot

PROPOSED LOCATION: NESE 15 100S 230E

Permit Tech Review: ☒

SURFACE: 2199 FSL 0339 FEL

Engineering Review: ☒

BOTTOM: 2425 FSL 0700 FEL

Geology Review: ☒

COUNTY: UINTAH

LATITUDE: 39.94771

LONGITUDE: -109.30424

UTM SURF EASTINGS: 644868.00

NORTHINGS: 4423120.00

FIELD NAME: NATURAL BUTTES

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU 38427

PROPOSED PRODUCING FORMATION(S): WASATCH-MESA VERDE

SURFACE OWNER: 1 - Federal

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

- ☒ **PLAT**
- ☒ **Bond:** FEDERAL - WYB000291
- ☐ **Potash**
- ☐ **Oil Shale 190-5**
- ☐ **Oil Shale 190-3**
- ☐ **Oil Shale 190-13**
- ☒ **Water Permit:** Permit #43-8496
- ☐ **RDCC Review:**
- ☐ **Fee Surface Agreement**
- ☒ **Intent to Commingle**


Commingle Approved

LOCATION AND SITING:

- ☐ **R649-2-3.**
- Unit:**
- ☐ **R649-3-2. General**
- ☒ **R649-3-3. Exception**
- ☒ **Drilling Unit**
- Board Cause No:** Cause 179-14
- Effective Date:** 6/12/2008
- Siting:** 460' fr ext. drilling unit boundary
- ☒ **R649-3-11. Directional Drill**

Comments: Presite Completed

Stipulations:
1 - Exception Location - dmason
3 - Commingle - ddoucet
4 - Federal Approval - dmason
15 - Directional - dmason



State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: Bonanza 1023-1512AS
API Well Number: 43047507420000
Lease Number: UTU 38427
Surface Owner: FEDERAL
Approval Date: 9/29/2009

Issued to:

KERR-MCGEE OIL & GAS ONSHORE, L.P., P.O. Box 173779, Denver, CO 80217

Authority:

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 179-14. The expected producing formation or pool is the WASATCH-MESA VERDE Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

Exception Location:

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

Commingle:

In accordance with Board Cause No. 179-14, commingling of the production from the Wasatch formation and the Mesaverde formation in this well is allowed.

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well – contact Carol Daniels at 801-538-5284 (please leave a voicemail message if not available)

OR


submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at <https://oilgas.ogm.utah.gov>

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) – due within 5 days of spudding the well
- Monthly Status Report (Form 9) – due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) – due prior to implementation
- Written Notice of Emergency Changes (Form 9) – due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) – due prior to implementation
- Report of Water Encountered (Form 7) – due within 30 days after completion
- Well Completion Report (Form 8) – due within 30 days after completion or plugging

Approved By:

A handwritten signature in black ink, appearing to read "Gil Hunt", with a stylized, flowing script.

Gil Hunt
Associate Director, Oil & Gas

RECEIVED

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SEP 18 2009
MC

FORM APPROVED
OMB No. 1004-0136
Expires July 31, 2010

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. UTU38427
1b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator KERRMCGEE OIL&GAS ONSHORE LP Contact: DANIELLE E PIERNOT Email: Danielle.Piernot@anadarko.com		7. If Unit or CA Agreement, Name and No.
3a. Address PO BOX 173779 DENVER, CO 80202-3779		8. Lease Name and Well No. BONANZA 1023-1512AS
3b. Phone No. (include area code) Ph: 720-929-6156 Fx: 720-929-7156		9. API Well No. 43 047 50742
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface NESE 2199FSL 339FEL 39.94778 N Lat, 109.30481 W Lon At proposed prod. zone NESE 2425FSL 700FEL 39.94841 N Lat, 109.30613 W Lon		10. Field and Pool, or Exploratory NATURAL BUTTES
14. Distance in miles and direction from nearest town or post office* APPROXIMATELY 33 MILES SOUTHEAST OF OURAY, UTAH		11. Sec., T., R., M., or Blk. and Survey or Area Sec 15 T10S R23E Mer SLB
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 700 FEET	16. No. of Acres in Lease 640.00	12. County or Parish UINTAH
18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. APPROXIMATELY 445 FEET	19. Proposed Depth 7951 MD 7900 TVD	13. State UT
21. Elevations (Show whether DF, KB, RT, GL, etc.) 5604 GL	22. Approximate date work will start 09/28/2009	17. Spacing Unit dedicated to this well
		20. BLM/BIA Bond No. on file WYB000291
		23. Estimated duration 60-90 DAYS

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification
- Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature (Electronic Submission)	Name (Printed/Typed) DANIELLE E PIERNOT Ph: 720-929-6156	Date 09/11/2009
--	---	--------------------

Title
REGULATORY ANALYST I

Approved by (Signature) 	Name (Printed/Typed) Stephanie J Howard	Date 12/3/09
Title Assistant Field Manager Lands & Mineral Resources	Office VERNAL FIELD OFFICE	

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Additional Operator Remarks (see next page)

Electronic Submission #74182 verified by the BLM Well Information System
For KERRMCGEE OIL&GAS ONSHORE LP, sent to the Vernal
Committed to AFMSS for processing by ROBIN R. HANSEN on 09/14/2009

NOTICE OF APPROVAL
RECEIVED

DEC 07 2009

DIV. OF OIL, GAS & MINING

** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED **

096XT4325AE

11AS 5-2-A9

UDOGM



UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
VERNAL FIELD OFFICE

170 South 500 East

VERNAL, UT 84078

(435) 781-4401



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company: Kerr McGee Oil & Gas Onshore Location: NESE, Sec. 15, T10S, R23E (S)
NESE, Sec. 15, T10S, R23E (B)
Well No: Bonanza 1023-15I2AS Lease No: UTU-38427
API No: 43-047-50742 Agreement: N/A

OFFICE NUMBER: (435) 781-4400
OFFICE FAX NUMBER: (435) 781-3420

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. This permit was processed using a 390 CX tied to NEPA approved 02/05/07. Therefore, this permit is approved for a two (2) year period OR until lease expiration OR the well must be spud by 02/05/12 (5 years from the NEPA approval date), whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.

NOTIFICATION REQUIREMENTS

Location Construction (Notify Environmental Scientist)	- Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify Environmental Scientist)	- Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	- Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to running casing and cementing all casing strings to: ut_vn_opreport@blm.gov .
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	- Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

***SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)***

- All new and replacement internal combustion gas field engines of less than or equal to 300 design-rated horsepower must not emit more than 2 gms of NO_x per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower.
- All and replacement internal combustion gas field engines of greater than 300 design rated horsepower must not emit more than 1.0 gms of NO_x per horsepower-hour.
- If there is an active Gilsonite mining operation within 2 miles of the well location, operator shall notify the Gilsonite operator at least 48 hours prior to any blasting during construction.
- If paleontological materials are uncovered during construction, the operator is to immediately stop work and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation may be necessary for the discovered paleontologic material before construction can continue.

SITE SPECIFIC COAs:

- As agreed upon the onsite the following seed mix will be used for Interim Reclamation:

Interim Reclamation seed mix

Ephraim crested wheatgrass	<i>Agropyron cristatum v. Epharim</i>	1 lbs. /acre
bottlebrush squirreltail	<i>Elymus elymoides</i>	1 lbs. /acre
Siberian wheatgrass	<i>Agropyron fragile</i>	1 lbs. /acre
western wheatgrass	<i>Agropyron smithii</i>	1 lbs. /acre
scarlet globemallow	<i>Spaeralcea coccinea</i>	1 lbs. /acre
shadscale	<i>Atriplex confertifolia</i>	2 lbs. /acre
fourwing saltbush	<i>Atriplex canescens</i>	2 lbs. /acre

Seed shall be applied with a rangeland drill, unless topography and /or rockiness precludes the use of equipment. Seed shall be applied between August 15 and ground freezing. All seed rates are in terms of Pure Live Seed. Operator shall notify the Authorized Officer when seeding has commenced, and shall retain all seed tags.

- The operator will control noxious weeds along the well pad, access road, and the pipeline route by spraying or mechanical removal. On BLM administered land, a Pesticide Use Proposal (PUP) will be submitted and approved prior to the application of herbicides or pesticides or possibly hazardous chemicals.
- The development of the well pad will not be seen from the White River corridor.

***DOWNHOLE PROGRAM
CONDITIONS OF APPROVAL (COAs)***

SITE SPECIFIC DOWNHOLE COAs:

- A Gama Ray Log shall be run from TD to surface.

Variances Granted:

Air Drilling:

- Properly lubricated and maintained rotating head, variance granted to use a properly maintained and lubricated diverter bowl in place of a rotating head.
- Blooie line discharge 100' from the well bore, variance granted for blooie line discharge to be 45' from the well bore.
- Compressors located in the opposite direction from the blooie line a minimum of 100' from the well bore. Variance granted for two truck/trailer mounted air compressors located within 40 feet from the well bore and 60' from the blooie line.
- In lieu of mud products on location, Kerr McGee will fill the reserve pit with water for kill fluid.
- Automatic igniter. Variance granted for igniter due to there being no productive formations while drilling with air.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.

- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.
- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in LAS format to UT_VN_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

OPERATING REQUIREMENT REMINDERS:

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- In accordance with 43 CFR 3162.4-3, this well shall be reported on the "Monthly Report of Operations" (Oil and Gas Operations Report ((OGOR)) starting with the month in which operations commence and continue each month until the well is physically plugged and abandoned. This report shall be filed in duplicate, directly with the Minerals Management Service, P.O. Box 17110, Denver, Colorado 80217-0110, or call 1-800-525-7922 (303) 231-3650 for reporting information.
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
 - Operator name, address, and telephone number.
 - Well name and number.
 - Well location (1/4¹/₄, Sec., Twn, Rng, and P.M.).
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - Unit agreement and/or participating area name and number, if applicable.
 - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.

- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.
- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.

- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: **KERR-McGEE OIL & GAS ONSHORE, L. P.**

Well Name: **BONANZA 1023-15I2AS**

Api No: **43-047-50742** Lease Type: **FEDERAL**

Section **15** Township **10S** Range **23E** County **UINTAH**

Drilling Contractor **PETE MARTIN DRLG** RIG # **BUCKET**

SPUDDED:

Date **01/31/2010**

Time **12:00 NOON**

How **DRY**

Drilling will Commence: _____

Reported by **JAMES GOBER**

Telephone # **(435) 828-7024**

Date **02/01/2010** Signed **CHD**

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU 38427
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: Bonanza 1023-15I2AS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2199 FSL 0339 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESE Section: 15 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047507420000
PHONE NUMBER: 720 929-6007 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
<input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 1/31/2010	<input type="checkbox"/> CHANGE WELL STATUS	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> ALTER CASING	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> OTHER:	
	<input type="checkbox"/> CASING REPAIR	
	<input type="checkbox"/> CHANGE WELL NAME	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> APD EXTENSION	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.		
MIRU PETE MARTIN BUCKET RIG. DRILLED 20" CONDUCTOR HOLE TO 40'. RAN 14" SCHEDULE 10 PIPE. CMT W/28 SX READY MIX. SPUD WELL LOCATION ON 01/31/2010 AT 14:00 HRS.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY February 16, 2010		
NAME (PLEASE PRINT) Andy Lytle	PHONE NUMBER 720 929-6100	TITLE Regulatory Analyst
SIGNATURE N/A	DATE 2/1/2010	

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: KERR MCGEE OIL & GAS ONSHORE LP
Address: P.O. Box 173779
city DENVER
state CO zip 80217

Operator Account Number: N 2995

Phone Number: (720) 929-6100

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304750744	BONANZA 1023-15P1BS		NESE	15	10S	23E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
<u>A</u>	99999	<u>17491</u>	1/31/2010			<u>2/18/10</u>	
Comments: MIRU PETE MARTIN BUCKET RIG. <u>WSMVD</u> SPUD WELL LOCATION ON 1/31/2010 AT 10:00 HRS. <u>BHL = SESE</u>							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304750741	BONANZA 1023-15H4CS		NESE	15	10S	23E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
<u>A</u>	99999	<u>17492</u>	1/31/2010			<u>2/18/10</u>	
Comments: MIRU PETE MARTIN BUCKET RIG. <u>WSMVD</u> SPUD WELL LOCATION ON 1/31/2010 AT 12:00 HRS. <u>BHL = SENE</u>							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304750742	BONANZA 1023-15I2AS		NESE	15	10S	23E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
<u>A</u>	99999	<u>17493</u>	1/31/2010			<u>2/18/10</u>	
Comments: MIRU PETE MARTIN BUCKET RIG. <u>WSMVD</u> SPUD WELL LOCATION ON 1/31/2010 AT 14:00 HRS. <u>BHL = NESE</u>							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

RECEIVED
FEB 01 2010

ANDY LYTLE

Name (Please Print)


Signature

REGULATORY ANALYST

Title

2/1/2010

Date

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU 38427			
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME:			
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: Bonanza 1023-15I2AS			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2199 FSL 0339 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESE Section: 15 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047507420000			
PHONE NUMBER: 720 929-6007 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES			
COUNTY: UTAH		STATE: UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION				
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 2/22/2010 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input checked="" type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input checked="" type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER:
<input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input checked="" type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER:			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Kerr-McGee Oil & Gas Onshore LP (Kerr-McGee) respectfully requests to change the surface casing size for this well from FROM: 9-5/8" TO: 8-5/8". Additionally, Kerr-McGee requests to change the cement program for this well due to a revised drilling procedure. The production casing will still be cemented it's entire length to the surface. Please see the attached drilling program for additional details. All other information remains the same. Please contact the undersigned with any questions and/or comments. Thank you.					
Accepted by the Utah Division of Oil, Gas and Mining Date: February 17, 2010 By: 					
NAME (PLEASE PRINT) Danielle Piernot		PHONE NUMBER 720 929-6156			
TITLE Regulatory Analyst		DATE 2/16/2010			
SIGNATURE N/A					

KERR-McGEE OIL & GAS ONSHORE LP
DRILLING PROGRAM

COMPANY NAME	KERR-McGEE OIL & GAS ONSHORE LP	DATE	February 16, 2010		
WELL NAME	Bonanza 1023-15I2AS	TD	7,900'	TVD	7,951' MD
FIELD	Natural Buttes	COUNTY	Uintah	STATE	Utah
				FINISHED ELEVATION	5,603'
SURFACE LOCATION	NE/4 SE/4	2,199' FSL	339' FEL	Sec 15	T 10S R 23E
	Latitude:	39.947778	Longitude:	-109.304814	NAD 83
BTM HOLE LOCATION	NE/4 SE/4	2,425' FSL	700' FEL	Sec 15	T 10S R 23E
	Latitude:	39.948411	Longitude:	-109.306133	NAD 83
OBJECTIVE ZONE(S)	Wasatch/Mesaverde				
ADDITIONAL INFO	Regulatory Agencies: BLM (Minerals), BLM (Surface), UDOGM Tri-County Health Dept.				

GEOLOGICAL			MECHANICAL		
LOGS	FORMATION TOPS	DEPTH	HOLE SIZE	CASING SIZE	MUD WEIGHT
		40'		14"	
			11"	8-5/8", 28#, IJ-55, LTC	Air mist
<p>All water flows encountered while drilling will be reported to the appropriate agencies.</p>					
	Green River @	970'			
	Top of Birds Nest @	1,329'			
	Mahogany @	1,828'			
	Preset f/ GL @	1,980'			
	MD				
<p>Note: 11" surface hole will usually be drilled ±400' below the lost circulation zone (aka bird's nest). Drilled depth may be ±200' of the estimated set depth depending on the actual depth of the loss zone.</p>					
	Wasatch @	3,971'			
<p>Mud logging program TBD Cased hole logging program from TD - surf csg</p>					
			7-7/8"	4-1/2" 11.6# I-80 or equivalent BTC csg	Water / Fresh Water Mud 8.3-11.6 ppg
	Mverde @	5,743' TVD			
	MVU2 @	6,729' TVD			
	MVU1 @	7,330' TVD			
<p>Max anticipated Mud required 11.6 ppg</p>					
	TD @	7,900' TVD 7,951' MD			



KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM

CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'						
						3,390	1,880	348,000
SURFACE	8-5/8"	0 to 1,980	28.00	IJ-55	LTC	1.11	2.03	6.21
						7,780	6,350	278,000
PRODUCTION	4-1/2"	0 to 7,951	11.60	I-80	BTC	2.57	1.33	3.45

*Burst on surface casing is controlled by fracture gradient as shoe with gas gradient above.

D.F. = 2.72

1) Max Anticipated Surf. Press.(MASP) (Surface Casing) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

2) MASP (Prod Casing) = Pore Pressure at TD - (0.22 psi/ft-partial evac gradient x TD)

(Burst Assumptions: TD = 11.6 ppg)

0.22 psi/ft = gradient for partially evac wellbore

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

MASP 2,938 psi

3) Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

(Burst Assumptions: TD = 11.6 ppg)

0.59 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

MABHP 4,706 psi

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	500'	Premium cmt + 2% CaCl	215	60%	15.60	1.18
			+ 0.25 pps flocele				
Option 1							
	TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	260	0%	15.60	1.18
			+ 2% CaCl + 0.25 pps flocele				
			Premium cmt + 2% CaCl				
SURFACE			NOTE: If well will circulate water to surface, option 2 will be utilized				
Option 2	LEAD	1,480'	65/35 Poz + 6% Gel + 10 pps gilsonite	290	35%	12.60	1.81
			+ 0.25 pps Flocele + 3% salt BWOW				
	TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.60	1.18
			+ 0.25 pps flocele				
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
PRODUCTION	LEAD	5,291'	Premium Lite II +0.25 pps	450	40%	11.00	3.38
			celloflake + 5 pps gilsonite + 10% gel				
			+ 0.5% extender				
	TAIL	2,660'	50/50 Poz/G + 10% salt + 2% gel	660	40%	14.30	1.31
			+ 0.1% R-3				

*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. No centralizers will be used.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

John Huycke / Emile Goodwin

DATE:

DRILLING SUPERINTENDENT:

John Merkel / Lovel Young

DATE:

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU 38427
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: Bonanza 1023-15I2AS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2199 FSL 0339 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESE Section: 15 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047507420000
PHONE NUMBER: 720 929-6007 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 3/23/2010	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER	
	OTHER:	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. FINISHED DRILLING FROM 1950' TO 8010' ON 3/21/2010. RAN 4-1/2" 11.6# I-80 PRODUCTION CASING. PUMPED 40 BBLS WATER AHEAD. LEAD CMT W/610 SX CLASS G PREM LITE @ 12.0 PPG, 2.30 YIELD. TAILED CMT W/621 SX CLASS G 50/50 POZ MIX @ 14.3 PPG, 1.31 YIELD. DISPLACED W/1200 BBLS WATER, BUMPED PLUG, FLOATS HELD, 1 BBL BACK TO TRUCK, FINAL LIFT PSI 1850. L/D LANDING JT. FLUSH BOP, NIPPLE DOWN BOP, CLEAN MUD TANKS. RELEASED ENSIGN RIG 146 @ 11:00 HRS ON 3/23/2010.		
<div style="text-align: right;"> Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY March 24, 2010 </div>		
NAME (PLEASE PRINT) Andy Lytle	PHONE NUMBER 720 929-6100	TITLE Regulatory Analyst
SIGNATURE N/A	DATE 3/24/2010	

<div>STATE OF UTAH</div> <div>DEPARTMENT OF NATURAL RESOURCES</div> <div>DIVISION OF OIL, GAS, AND MINING</div>		<div>FORM 9</div> <div>5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 38427</div>	
<div>SUNDRY NOTICES AND REPORTS ON WELLS</div> <div>Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.</div>		<div>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</div> <div>7.UNIT or CA AGREEMENT NAME:</div>	
<div>1. TYPE OF WELL</div> <div>Gas Well</div>		<div>8. WELL NAME and NUMBER:</div> <div>Bonanza 1023-15I2AS</div>	
<div>2. NAME OF OPERATOR:</div> <div>KERR-MCGEE OIL & GAS ONSHORE, L.P.</div>		<div>9. API NUMBER:</div> <div>43047507420000</div>	
<div>3. ADDRESS OF OPERATOR:</div> <div>P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779</div>		<div>PHONE NUMBER:</div> <div>720 929-6007 Ext</div>	<div>9. FIELD and POOL or WILDCAT:</div> <div>NATURAL BUTTES</div>
<div>4. LOCATION OF WELL</div> <div>FOOTAGES AT SURFACE:</div> <div>2199 FSL 0339 FEL</div> <div>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</div> <div>Qtr/Qtr: NESE Section: 15 Township: 10.0S Range: 23.0E Meridian: S</div>		<div>COUNTY:</div> <div>UINTAH</div>	
		<div>STATE:</div> <div>UTAH</div>	
<div>11.</div> <div>CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</div>			
TYPE OF SUBMISSION		TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:		<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:		<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:		<input type="checkbox"/> CASING REPAIR	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 5/5/2010		<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
		<input type="checkbox"/> CHANGE TUBING	
		<input type="checkbox"/> CHANGE WELL STATUS	
		<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
		<input type="checkbox"/> DEEPEN	
		<input type="checkbox"/> FRACTURE TREAT	
		<input type="checkbox"/> OPERATOR CHANGE	
		<input type="checkbox"/> PLUG AND ABANDON	
		<input type="checkbox"/> PLUG BACK	
		<input checked="" type="checkbox"/> PRODUCTION START OR RESUME	
		<input type="checkbox"/> RECLAMATION OF WELL SITE	
		<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
		<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
		<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
		<input type="checkbox"/> TEMPORARY ABANDON	
		<input type="checkbox"/> TUBING REPAIR	
		<input type="checkbox"/> VENT OR FLARE	
		<input type="checkbox"/> WATER DISPOSAL	
		<input type="checkbox"/> WATER SHUTOFF	
		<input type="checkbox"/> SI TA STATUS EXTENSION	
		<input type="checkbox"/> APD EXTENSION	
		<input type="checkbox"/> WILDCAT WELL DETERMINATION	
		<input type="checkbox"/> OTHER:	
<div>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</div> <div>THE SUBJECT WELL WAS PLACED ON PRODUCTION ON 5-5-2010 AT 11:00 A.M. THE CHRONOLOGICAL WELL HISTORY WILL BE SUBMITTED WITH THE WELL COMPLETION REPORT.</div> <div>Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY May 06, 2010</div>			
NAME (PLEASE PRINT)		PHONE NUMBER	TITLE
Andy Lytle		720 929-6100	Regulatory Analyst
SIGNATURE		DATE	
N/A		5/5/2010	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU 38427
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: Bonanza 1023-15I2AS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2199 FSL 0339 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESE Section: 15 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047507420000
PHONE NUMBER: 720 929-6007 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 3/23/2010	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER	
	OTHER:	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. FINISHED DRILLING FROM 1950' TO 8010' ON 3/21/2010. RAN 4-1/2" 11.6# I-80 PRODUCTION CASING. PUMPED 40 BBLS WATER AHEAD. LEAD CMT W/610 SX CLASS G PREM LITE @ 12.0 PPG, 2.30 YIELD. TAILED CMT W/621 SX CLASS G 50/50 POZ MIX @ 14.3 PPG, 1.31 YIELD. DISPLACED W/1200 BBLS WATER, BUMPED PLUG, FLOATS HELD, 1 BBL BACK TO TRUCK, FINAL LIFT PSI 1850. L/D LANDING JT. FLUSH BOP, NIPPLE DOWN BOP, CLEAN MUD TANKS. RELEASED ENSIGN RIG 146 @ 11:00 HRS ON 3/23/2010.		
<div style="text-align: right;"> Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY March 24, 2010 </div>		
NAME (PLEASE PRINT) Andy Lytle	PHONE NUMBER 720 929-6100	TITLE Regulatory Analyst
SIGNATURE N/A	DATE 3/24/2010	

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

COPY

FORM APPROVED
OMB No. 1004-0137
Expires: July 31, 2010

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Dry <input type="checkbox"/> Other			6. If Indian, Allottee or Tribe Name		
b. Type of Completion <input checked="" type="checkbox"/> New Well <input type="checkbox"/> Work Over <input type="checkbox"/> Deepen <input type="checkbox"/> Plug Back <input type="checkbox"/> Diff. Resvr. Other _____			7. Unit or CA Agreement Name and No.		
2. Name of Operator KERR-MCGEE OIL&GAS ONSHORE			8. Lease Name and Well No. BONANZA 1023-1512AS		
3. Address P.O. BOX 173779 DENVER, CO 80217			9. API Well No. 43-047-50742		
3a. Phone No. (include area code) Ph: 720-929-6100			10. Field and Pool, or Exploratory NATURAL BUTTES		
4. Location of Well (Report location clearly and in accordance with Federal requirements)* At surface NESE 2199FSL 339FEL 39.94778 N Lat, 109.30481 W Lon At top prod interval reported below NESE 2438FSL 717FEL At total depth NESE 2419FSL 695FEL			11. Sec., T., R., M., or Block and Survey or Area Sec 15 T10S R23E Mer SLB		
14. Date Spudded 01/31/2010			15. Date T.D. Reached 03/21/2010		
16. Date Completed <input type="checkbox"/> D & A <input checked="" type="checkbox"/> Ready to Prod. 05/05/2010			17. Elevations (DF, KB, RT, GL)* 5603 GL		
18. Total Depth: MD 8010 TVD 7954			19. Plug Back T.D.: MD 7955 TVD 7901		
20. Depth Bridge Plug Set: MD TVD			21. Type Electric & Other Mechanical Logs Run (Submit copy of each) GR/CBL-HDIL/ZDL/CN/GR		
22. Was well cored? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis) Was DST run? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis) Directional Survey? <input type="checkbox"/> No <input checked="" type="checkbox"/> Yes (Submit analysis)					

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sks. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
20.000	14.000 STEEL	36.7		40		28			
11.000	8.625 IJ55	28.0		1915		675			
7.875	4.500 I80	11.6		8000		1235		108	

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2.375	7305							

25. Producing Intervals

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) MESAVERDE	6414	7787	6414 TO 7787	0.360	126	OPEN
B)						
C)						
D)						

26. Perforation Record

27. Acid, Fracture, Treatment, Cement Squeeze, Etc.

Depth Interval	Amount and Type of Material
6414 TO 7787	PMP 7,820 BBLs SLICK H2O & 304,321 LBS 30/50 SD.

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
05/05/2010	05/21/2010	24	→	0.0	1341.0	215.0			FLows FROM WELL
Choke Size	Tbg. Press. Flwg. 1020 SI	Csg. Press. 1504.0	24 Hr. Rate →	Oil BBL 0	Gas MCF 1341	Water BBL 215	Gas:Oil Ratio	Well Status PGW	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	

(See Instructions and spaces for additional data on reverse side)

ELECTRONIC SUBMISSION #87391 VERIFIED BY THE BLM WELL INFORMATION SYSTEM

** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED **

DIV. OF OIL, GAS & MINING

RECEIVED

JUN 08 2010

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	

29. Disposition of Gas(Sold, used for fuel, vented, etc.)
SOLD

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top Meas. Depth
GREEN RIVER BIRD'S NEST MAHOGANY WASATCH MESAVERDE	974 1215 1803 4035 5803	5803 8010	TD		

32. Additional remarks (include plugging procedure):

ATTACHED IS THE CHRONOLOGICAL WELL HISTORY AND FINAL SURVEY.

33. Circle enclosed attachments:

- | | | | |
|---|--------------------|---------------|-----------------------|
| 1. Electrical/Mechanical Logs (1 full set req'd.) | 2. Geologic Report | 3. DST Report | 4. Directional Survey |
| 5. Sundry Notice for plugging and cement verification | 6. Core Analysis | 7 Other: | |

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions):

**Electronic Submission #87391 Verified by the BLM Well Information System.
For KERR-MCGEE OIL&GAS ONSHORE, LP, sent to the Vernal**

Name (please print) ANDY LYTLETitle REGULATORY ANALYST

Signature _____ (Electronic Submission)

Date 06/03/2010

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ****

US ROCKIES REGION

Operation Summary Report

Well: BONANZA 1023-15I2AS (YELLOW) Spud Conductor: 1/31/2010 Spud Date: 2/7/2010

Project: UTAH-UINTAH Site: BONANZA 1023-15I PAD Rig Name No: ENSIGN 146/146, PROPETRO/

Event: DRILLING Start Date: 2/2/2010 End Date: 3/23/2010

Active Datum: RKB @5,618.01ft (above Mean Sea Level) UWI: NE/SE/0/10/S/23/E/15/0/0/6/PM/S/2,199.00/E/0/339.00/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
2/7/2010	16:00 - 19:00	3.00	MIRU	01	B	P		DRESS CONDUCTOR, INSTALL AIR BOWL, RIG UP BOWIE LINE, RIG UP RIG., BUILD DITCH, RIG UP PUMPS, DOG HOUSE, AIR COMPRESSOR AND BOOSTER. P/U 1.5 BENT HOUSE MOTOR SN 8022 AND Q507 SN 7018945 3RD RUN.
	19:00 - 20:00	1.00	DRLSUR	02	B	P		DRILL 44'-150'. SPUD 2/7/2010 19:00
	20:00 - 21:30	1.50	DRLSUR	06	A	P		LD 6" COLLARS AND P/U AND ORIENT SCIENTIFIC DIRECTIONAL TOOLS.
	21:30 - 0:00	2.50	DRLSUR	02	D	P		DRILL W/ MWD 150'- 690' (540', 216'/HR) WOB 5-20K, ROT 45, GPM 650, DH ROT 104, PSI 1000/1300, UP/DOWN//ROT 51/51/51.
2/8/2010	0:00 - 10:00	10.00	DRLSUR	02	D	P		DRILL 690'-1950' (1260', 126'/HR) TD 2/8/2010 10:00 WOB 25K, ROT 45, GPM 650, DH ROT 104, PSI 1300/1600, UP/DOWN//ROT 65/63/64. LOSS CIRC 1440', AERATE WATER W/ 250 GPM TO MAINTAIN PIT.
	10:00 - 14:00	4.00	CSG	05	F	P		CIRC CONDITION HOLE, CLEAN HOLE W/ AIR, AND BUILD VOLUME IN PIT.
	14:00 - 17:00	3.00	CSG	06	A	P		LDDS, LD/BHA, LD DIRECTIONAL TOOLS. LD BIT AND MOTOR.
	17:00 - 19:30	2.50	CSG	12	C	P		RUN 43 JTS OF 8-5/8" 28# IJ-55 CSG W/ 8RD LTC THREADS. RAN FLOAT SHOE ON SHOE JT LANDED @ 1905' KB. RAN BAFFLE PLATE IN TOP OF SHOE JT. BAFFLE @ 1859' KB. FILL CSG 800'.
	19:30 - 20:00	0.50	RDMO	01	E	P		RIG DOWN RIG, RELEASE RIG 20:00
	20:00 - 0:00	4.00	CSG	12	E	P		HELD SAFETY MTNG,PRESS TEST TO 2000 PSI,PUMP 100 BBLS H2O,PUMP 20 BBLS GEL WATER,PUMP (20 BBL) 200 SX 15.8 # 1.15 YLD 5 GAL/SK TAIL CMNT DROP PLUG ON FLY DISP W/ 114 BBLS FRESH WATER 60 PSI LIFT NO RETURNS, BUMP PLUG W / 560 PSI, TOP OUT 100 SX OF 15.8#. 1.15 YLD 5 GAL SK 4% CALC CMNT, WAIT 2 HRS PUMP 50 SX SAME CMNT. WAITED 24 HRS AND PUMP 425 SX OF SAME CEMENT. CEMENT TO SURFACE AND STAYING.
3/19/2010	0:00 - 1:00	1.00	DRLPRO	01	C	P		SKID RIG OVER THE 15I2AS
	1:00 - 2:00	1.00	DRLPRO	14	A	P		NIPPLE UP BOP
	2:00 - 4:00	2.00	DRLPRO	15	A	P		TEST BOP RAMS, CHOKE, KILLINE, HCR TO 5000 PSI, 250 LOW, ANN 2500, 250 LOW, CASING 1500 PSI
	4:00 - 6:30	2.50	DRLPRO	06	A	P		P/U NEW BIT, INSTALL MWD & R.I.H, TAG CMT. @ 1816 FT.
	6:30 - 7:30	1.00	DRLPRO	07	B	P		LEVEL RIG & INSTALL ROTATING HEAD
	7:30 - 10:00	2.50	DRLPRO	02	F	P		DRILL CMT, FLOAT & SHOE
	10:00 - 18:00	8.00	DRLPRO	02	D	P		DRILL & SLIDE F/ 1960 TO 2826 - 866 FT. 108 FT. PER/HR, WOB 20, RPM 30, MMRPM 140, GPM 500, PSI ON BTM 1400, OFF 1050
	18:00 - 18:30	0.50	DRLPRO	07	A	P		RIG SERVICE
	18:30 - 0:00	5.50	DRLPRO	02	D	P		DRILL & SLIDE F/ 2826 TO 3535 - 709 FT. 129 FT. PER/HR, WOB 18, RPM 30, MMRPM 140, GPM 500, PSI ON BTM. 1450, OFF 1100
3/20/2010	0:00 - 15:00	15.00	DRLPRO	02	D	P		DRILL & SLIDE F/ 3535 TO 5545 - 2010 FT. 134 FT. PER/HR. - WOB 20, RPM 30, MMRPM 140, GPM 500, PSI ON BTM. 1600 OFF 1200
	15:00 - 15:30	0.50	DRLPRO	07	A	P		RIG SERVICE

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-15I2AS (YELLOW)	Spud Conductor: 1/31/2010	Spud Date: 2/7/2010
Project: UTAH-UINTAH	Site: BONANZA 1023-15I PAD	Rig Name No: ENSIGN 146/146, PROPETRO/
Event: DRILLING	Start Date: 2/2/2010	End Date: 3/23/2010
Active Datum: RKB @5,618.01ft (above Mean Sea Level) UWI: NE/SE/0/10/S/23/E/15/0/0/6/PM/S/2,199.00/E/0/339.00/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
3/21/2010	15:30 - 0:00	8.50	DRLPRO	02	D	P		DRILL & SLIDE F/ 5545 TO 6389 - 844 FT. 99 FT. PER/HR, WOB 18, RPM 35, MMRPM 131, GPM 470, PSI ON BTM 2200 OFF 1800
	0:00 - 14:30	14.50	DRLPRO	02	D	P		DRILL F/ 6389 TO 7540 - 1151 FT. 79 FT. PER/HR. MW 11.8, VIS 41, WOB 20, RPM 40, MMRPM 131, GPM 470, PSI ON BTM. 2350, OFF 1850
	14:30 - 15:00	0.50	DRLPRO	07	A	P		RIG SERVICE
	15:00 - 21:00	6.00	DRLPRO	02	D	P		DRILL F/ 7540 TO 8010 - 470 FT. 78 FT. PER/HR. MW 11.9, VIS 41, WOB 20, RPM 40, MMRPM 131, GPM 470, PSI ON BTM. 2600, OFF 2100
3/22/2010	21:00 - 22:00	1.00	DRLPRO	05	C	P		CIRC. FOR WIPER TRIP
	22:00 - 0:00	2.00	DRLPRO	06	E	P		FLOW CHECK, NO FLOW, WIPER TRIP TO SHOE
	0:00 - 8:00	8.00	DRLPRO	06	E	P		WIPER TRIP TO SHOE
	8:00 - 9:30	1.50	DRLPRO	05	C	P		CIRC. 2 BTMS UP
	9:30 - 16:30	7.00	DRLPRO	06	B	P		FLOW CHECK, NO FLOW, PUMP 3 STDS. OUT & PUMP SLUG, T.O.H TO RUN LOGS
	16:30 - 17:00	0.50	DRLPRO	06	J	P		PULL WEAR RING
	17:00 - 22:00	5.00	DRLPRO	11	D	P		RIGGED UP & RAN OPEN HOLE LOGS TO 7997 FT. RIGGED DOWN
	22:00 - 0:00	2.00	DRLPRO	12	C	P		HELD SAFETY MEETING, RIGGED UP & RAN 4 1/2 CASING
3/23/2010	0:00 - 6:00	6.00	DRLPRO	12	C	P		RUN 189 JTS. 4 1/2 I-80 BTC CASING, LANDED @ 8000.31 FT. FLOAT COLLAR @ 7955.21, RIG DOWN CASING CREW
	6:00 - 7:00	1.00	DRLPRO	05	D	P		CIRC. THROUGH CASING
	7:00 - 9:30	2.50	DRLPRO	12	E	P		HELD SAFETY MEETING W/ BJ SERVICES RIGGED UP & PUMPED 40 BBLS. WATER AHEAD, LEAD W/ 610 SKS.249 BBLS. 12# 2.30 YIELD, TAIL W/ 625 SKS. 146 BBLS. 14.3# 1.31 YIELD & DISPLACED W/ 124 BBLS WATER, BUMPED PLUG, FLOATS HELD, 1 BBL BACK TO TRUCK, FINAL LIFT PSI 1850
	9:30 - 11:00	1.50	DRLPRO	14	A	P		L/D LANDING JT. FLUSH BOP, NIPPLE DOWN BOP, CLEAN MUD TANKS RIG RELEASED @ 11:00 HRS. 3/23/2010

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-15I2AS (YELLOW)		Spud Conductor: 1/31/2010		Spud Date: 2/7/2010	
Project: UTAH-UINTAH		Site: BONANZA 1023-15I PAD		Rig Name No: ENSIGN 146/146, PROPETRO/	
Event: DRILLING		Start Date: 2/2/2010		End Date: 3/23/2010	
Active Datum: RKB @5,618.01ft (above Mean Sea Leve		UWI: NE/SE/0/10/S/23/E/15/0/0/6/PM/S/2,199.00/E/0/339.00/0/0			

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	11:00 - 11:00	0.00	DRLPRO					<p>CONDUCTOR CASING: Cond. Depth set: 44 Cement sx used:</p> <p>SPUD DATE/TIME: 2/7/2010 19:00</p> <p>SURFACE HOLE: Surface From depth:44 Surface To depth: 1,950 Total SURFACE hours: 13.50 Surface Casing size:8 5/8 # of casing joints ran: 43 Casing set MD:1,905.0 # sx of cement:350 Cement blend (ppg):15.8 Cement yield (ft3/sk): 1.15 # of bbls to surface: 0 Describe cement issues: TOP OUT 100 SX, WAIT 2HRS, 50 SX, NO CEMENT TO SURFACE Describe hole issues:</p> <p>PRODUCTION: Rig Move/Skid start date/time: 3/19/2010 0:00 Rig Move/Skid finish date/time:3/19/2010 1:00 Total MOVE hours: 1.0 Prod Rig Spud date/time: 3/19/2010 7:30 Rig Release date/time: 3/23/2010 11:00 Total SPUD to RR hours:99.5 Planned depth MD 8,009 Planned depth TVD 7,960 Actual MD: 8,010 Actual TVD: 7,955 Open Wells \$: \$479,735 AFE \$: \$625,830 Open wells \$/ft:\$59.89</p> <p>PRODUCTION HOLE: Prod. From depth: 1,960 Prod. To depth:8,010 Total PROD hours: 57.5 Log Depth: 8722 Production Casing size: 4 1/2 # of casing joints ran: 189 Casing set MD:8,000.3 # sx of cement:1,235 Cement blend (ppg):L 12 T 14.3 Cement yield (ft3/sk): L 2.30 T 1.31 Est. TOC (Lead & Tail) or 2 Stage : 4930 Describe cement issues: Describe hole issues:</p> <p>DIRECTIONAL INFO: KOP: 150 Max angle: 23.05 Departure: 429.05 Max dogleg MD: 4.52</p>

US ROCKIES REGION

Operation Summary Report

Well: BONANZA 1023-1512AS (YELLOW) Spud Conductor: 1/31/2010 Spud Date: 2/7/2010

Project: UTAH-UINTAH Site: BONANZA 1023-151 PAD Rig Name No: MILES-GRAY 1/1

Event: COMPLETION Start Date: 4/26/2010 End Date: 5/4/2010

Active Datum: RKB @5,618.01ft (above Mean Sea Leve UWI: NE/SE/0/10/S/23/E/15/0/0/6/PM/S/2,199.00/E/0/339.00/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
4/23/2010	8:00 - 8:30	0.50	COMP	48		P		HSM. RIGGING UP ON A PAD W / TWO SETS OF EQUIPMENT.
	8:30 - 9:30	1.00	COMP	37	C	P		MIRU B&C QUICK TEST & PRESSURE TEST CASING & FRAC VALVES. RDMO B&C QUICK TEST.
4/26/2010								MIRU CUTTERS TO PERFORATE.
								PU 3 1/8" EXP GNS, 23 GRM, .36 HOLES, 120 DEG PHASING.
								PERF 7,785'-87' 3SPF, 7,672'-73' 3SPF, 7,654'-56' 3SPF, 7,578'-80' 3SPF, 21 HOLES.
								SWI SDFWE.
								HSM. FRACING & PERFORATING ON A PAD WELL
4/26/2010	6:30 - 7:00	0.50	COMP	48		P		MIRU SUPERIOR & CUTTERS. PRESSURE TEST SURFACE EQUIPMENT.
	11:30 - 12:30	1.00	COMP	36	B	P		STG 1) WHP 680 PSI, BRK 3,873 PSI @ 4.6 BPM, ISIP 2,597 PSI, FG .77.
								PUMP 100 BBLS @ 39.5 BPM @ 5,964 PSI = 87% HOLES OPEN.
								MP 0,000 PSI, MR 00.0 BPM, AP 0,000 PSI, AR 00.0 BPM, ISIP 0,000 PSI, FG .00, NPI 000 PSI.
								PUMP 0,000 BBLS OF SW & 00,000 LBS OF 30/50 SAND & 5,000 LBS OF 20/40 RESIN SAND. TOTAL PROP 00,000 LBS.
4/26/2010	14:12 - 14:42	0.50	COMP	36	B	P		STG 2) PU 4 1/2" HALL. CBP & 3 1/8" EXP GNS, 23 GRM, .36 HOLES, 120 DEG PHASING & RIH.
								SET CBP @ 7,556' & PERF 7,524'-26' 3SPF, 7,508'-09' 3SPF, 7,486'-88' 3SPF, 7,428'-29' 3SPF, 7,361'-62' 3SPF, 21 HOLES.
								WHP 881 PSI, BRK 3,656 PSI @ 4.8 BPM, ISIP 2,033 PSI, FG .70.
								PUMP 100 BBLS @ 50.7 BPM @ 5,600 PSI = 100% HOLES OPEN.
								MP 7,000 PSI, MR 50.7 BPM, AP 6,615 PSI, AR 46 BPM, ISIP 2,174 PSI, FG .72, NPI 141 PSI.
4/26/2010	15:00 - 16:00	1.00	COMP					PUMP 1,091 BBLS OF SW & 36,597 LBS OF 30/50 SAND & 5,000 LBS OF 20/40 RESIN SAND. TOTAL PROP 41,597 LBS.
								STG 3) PU 4 1/2" HALL. CBP & 3 1/8" EXP GNS, 23 GRM, .36 HOLES, 90 & 120 DEG PHASING & RIH.
								SET CBP @ 7,336' & PERF 7,304'-06' 4SPF, 7,290'-92' 3SPF, 7,190'-91' 3SPF, 7,100'-01' 4SPF, 21 HOLES.
								SWI SDFN.
								HSM. FRACING & PERFORATING ON A PAD WELL
4/27/2010	7:00 - 7:30	0.50	COMP	48		P		STG 3) WHP 1,040 PSI, BRK 3,102 PSI @ 4.8 BPM, ISIP 1,810 PSI, FG .69.
	7:40 - 8:36	0.93	COMP	36	B	P		PUMP 100 BBLS @ 38 BPM @ 6,200 PSI = 52% HOLES OPEN.
4/27/2010								MP 6,709 PSI, MR 52.2 BPM, AP 5,394 PSI, AR 46 BPM, ISIP 1,965 PSI, FG .71, NPI 155 PSI.
								PUMP 1,631 BBLS OF SW & 62,733 LBS OF 30/50 SAND & 5,000 LBS OF 20/40 RESIN SAND. TOTAL PROP 67,733 LBS.

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-15I2AS (YELLOW)	Spud Conductor: 1/31/2010	Spud Date: 2/7/2010
Project: UTAH-UINTAH	Site: BONANZA 1023-15I PAD	Rig Name No: MILES-GRAY 1/1
Event: COMPLETION	Start Date: 4/26/2010	End Date: 5/4/2010
Active Datum: RKB @5,618.01ft (above Mean Sea Leve		
UWI: NE/SE/0/10/S/23/E/15/0/0/6/PM/S/2,199.00/E/0/339.00/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	11:10 - 11:40	0.50	COMP	36	B	P		STG 4) PU 4 1/2" HALL. CBP & 3 1/8" EXP GNS, 23 GRM, .36 HOLES, 120 DEG PHASING & RIH. SET CBP @ 7,018' & PERF 6,984'-88' 3SPF, 6,894'-96' 3SPF, 6,858'-59' 3SPF, 21 HOLES. WHP 206 PSI, BRK 2,625 PSI @ 4.7 BPM, ISIP 1,180 PSI, FG .61. PUMP 100 BBLS @ 44 BPM @ 4,350 PSI = 61% HOLES OPEN. MP 6,995 PSI, MR 51.5 BPM, AP 5,417 PSI, AR 48.9 BPM, ISIP 1,750 PSI, FG .69, NPI 570 PSI. PUMP 1,385 BBLS OF SW & 51,872 LBS OF 30/50 SAND & 5,000 LBS OF 20/40 RESIN SAND. TOTAL PROP 56,872 LBS.
	14:50 - 15:40	0.83	COMP	36	B	P		STG 5) PU 4 1/2" HALL. CBP & 3 1/8" EXP GNS, 23 GRM, .36 HOLES, 90 & 120 DEG PHASING & RIH. SET CBP @ 6,790' & PERF 6,758'-60' 4SPF, 6,681'-82' 3SPF, 6,606'-08' 3SPF, 6,561'-62' 4PF, 21 HOLES. WHP 600 PSI, BRK 2,112 PSI @ 4.7 BPM, ISIP 1,150 PSI, FG .61. PUMP 100 BBLS @ 51.1 BPM @ 4,000 PSI = 95% HOLES OPEN. MP 5,245 PSI, MR 51.5 BPM, AP 3,715 PSI, AR 51 BPM, ISIP 1,720 PSI, FG .70, NPI 570 PSI. PUMP 2,142 BBLS OF SW & 79,822 LBS OF 30/50 SAND & 5,000 LBS OF 20/40 RESIN SAND. TOTAL PROP 84,822 LBS.
	15:45 - 16:45	1.00	COMP	37	C	P		STG 6) PU 4 1/2" HALL. CBP & 3 1/8" EXP GNS, 23 GRM, .36 HOLES, 120 DEG PHASING & RIH. SET CBP @ 6,501' & PERF 6,468'-71' 3SPF, 6,443'-45' 3SPF, 6,414'-16' 3SPF, 21 HOLES. SDFN
4/28/2010	6:30 - 7:00	0.50	COMP	48		P		HSM. FRACING & SETTING KILL PLG & RDMO
	7:40 - 8:05	0.42	COMP	36	B	P		STG 6) WHP 460 PSI, BRK 2,552 PSI @ 4.7 BPM, ISIP 1,325 PSI, FG .64. PUMP 100 BBLS @ 45 BPM @ 3,900 PSI = 100% HOLES OPEN. MP 4,769 PSI, MR 50 BPM, AP 4,063 PSI, AR 48 BPM, ISIP 1,700 PSI, FG .70, NPI 375 PSI. PUMP 788 BBLS OF SW & 25,345 LBS OF 30/50 SAND & 5,000 LBS OF 20/40 RESIN SAND. TOTAL PROP 35,345 LBS.
	8:05 - 9:00	0.92	COMP	34	I	P		KILL PLG) PU 4 1/2" HALLIBURTON CBP. RIH SET CBP @ 6,380'. RDMO.
5/4/2010	7:00 - 7:30	0.50	COMP	48		P		HSM, RIGGING DWN & UP AROUND FLOWING WELLS.
	7:30 - 9:30	2.00	COMP	30	A	P		RD OFF BON 1023-15H4CS, MOVE OVER & RIG UP. ND FRAC VALVES, NU WELL HEAD SECTION & BOPS. RU FLOOR & TBG EQUIP.
	9:30 - 14:30	5.00	COMP	31	I	P		TALLY & PU 37/8 BIT, POBS, 1.875 X/N, 201 JTS 23/8 L-80 OFF FLOAT, TAG UP @ 6354'. RU DRLG EQUIP.

US ROCKIES REGION
Operation Summary Report

Well: BONANZA 1023-15I2AS (YELLOW)	Spud Conductor: 1/31/2010	Spud Date: 2/7/2010
Project: UTAH-UINTAH	Site: BONANZA 1023-15I PAD	Rig Name No: MILES-GRAY 1/1
Event: COMPLETION	Start Date: 4/26/2010	End Date: 5/4/2010
Active Datum: RKB @5,618.01ft (above Mean Sea Level) UWI: NE/SE/0/10/S/23/E/15/0/0/6/PM/S/2,199.00/E/0/339.00/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	14:30 - 19:00	4.50	COMP	44	C	P		<p>BROKE CIRC CONVENTIONAL, TEST BOPS TO 3,000# PSI, RIH</p> <p>C/O 10' SAND TAG 1ST PLUG @ 6364' DRL PLG IN 3 MIN, 200# PSI INCREASE RIH.</p> <p>C/O 30' SAND TAG 2ND PLUG @ 6501' DRL PLG IN 3 MIN, 100# PSI INCREASE RIH.</p> <p>C/O 30' SAND TAG 3RD PLUG @ 6790' DRL PLG IN 7 MIN, 100# PSI INCREASE RIH.</p> <p>C/O 30' SAND TAG 4TH PLUG @ 7018' DRL PLG IN 4 MIN, 200# PSI INCREASE RIH.</p> <p>C/O 30' SAND TAG 5TH PLUG @ 7336' DRL PLG IN 3 MIN, 300# PSI INCREASE RIH.</p> <p>C/O 30' SAND TAG 6TH PLUG @ 7556' DRL PLG IN 3 MIN, 200# PSI INCREASE RIH.</p> <p>C/O TO PBTD @ 7955' CIRC CLEAN, RD SWIVEL. L/D 21 JTS 23/8 L-80, LAND TBG ON 231 JTS, ND BOPS NU WH. PMP OFF BIT LET WELL SET FOR 30 MIN TO LET BIT FALL, TURN WELL OVER TO FB CREW. (HIGH WINDS TODAY)</p> <p>KB = 13' WEATHERFORDS 71/16 5K HANGER = .83' 231 JTS 23/8 L-80 = 7289.89' POBS & 1.875 X/N = 2.20' EOT @ 7305.92'</p> <p style="text-align: right;">FTP = 50 PS SICP = 1400</p> <p>PSI 315 JTS HAULED OUT 231 LANDED 84 TO RETURN</p> <p>TWTR = 8020 BBLS TWR = 1000 BBLS TWLTR = 7020 BBLS</p>
5/5/2010	7:00 -			33	A			<p>7 AM FLBK REPORT: CP 2150#, TP 1400#, 20/64" CK, 55 BWPH, TRACE SAND, LIGHT GAS TTL BBLS RECOVERED: 1817 BBLS LEFT TO RECOVER: 6203</p>
	11:00 -		PROD	50				<p>WELL TURNED TO SALES @ 1100 ON 5/5/10 - 500 MCFD, 1272 BWPD, CP 2500#, FTP 1325#, CK 20/64"</p>
5/6/2010	7:00 -			33	A			<p>7 AM FLBK REPORT: CP 2450#, TP 1400#, 20/64" CK, 38 BWPH, TRACE SAND, 921 GAS TTL BBLS RECOVERED: 2922 BBLS LEFT TO RECOVER: 5098</p>
5/7/2010	7:00 -			33	A			<p>7 AM FLBK REPORT: CP 2300#, TP 1350#, 20/64" CK, 28 BWPH, TRACE SAND, - GAS TTL BBLS RECOVERED: 3721 BBLS LEFT TO RECOVER: 4299</p>
5/8/2010	7:00 -			33	A			<p>7 AM FLBK REPORT: CP 2150#, TP 1350#, 20/64" CK, 20 BWPH, TRACE SAND, - GAS TTL BBLS RECOVERED: 4259 BBLS LEFT TO RECOVER: 3761</p>



ANADARKO PETROLEUM CORP.

UINTAH COUNTY, UTAH (nad 27)

BONANZA 1023-15I PAD

Bonanza 1023-15I2AS

Bonanza 1023-15I2AS


Design: Bonanza 1023-15I2AS

Standard Survey Report

24 March, 2010



Weatherford®



FORMATION TOP DETAILS

TVDPath	MDPath	Formation
3970.00	4019.40	WASATCH
6769.00	6818.40	MESAVERDE

CASING DETAILS

TVD	MD	Name	Size
1903.55	1905.10	8 5/8"	8.62

SECTION DETAILS

MD	Inc	Azi	TVD	+N-S	+E-W	DLeg	TFace	VSec	Annotation
1899.00	2.46	303.33	1897.46	42.62	-50.15	0.00	0.00	65.10	Start 107.00 hold at 1899.00 MD
2006.00	2.46	303.33	2004.36	45.14	-53.98	0.00	0.00	69.69	Start DLS 3.00 TFO -3.41
2590.96	20.00	300.32	2575.87	103.01	-151.61	3.00	-3.41	183.15	Start 233.94 hold at 2590.96 MD
2824.90	20.00	300.32	2795.70	143.41	-220.69	0.00	0.00	263.15	Start Drop -2.00
3825.15	0.00	0.00	3775.75	230.68	-369.90	2.00	180.00	435.93	Start 4132.25 hold at 3825.15 MD
7957.40	0.00	0.00	7908.00	230.68	-369.90	0.00	0.00	435.93	TD at 7957.40

WELLBORE TARGET DETAILS (MAP CO-ORDINATES AND LAT/LONG)



Name	TVD	+N-S	+E-W	Latitude	Longitude	Shape
PBHL	7908.00	230.68	-369.90	39° 56' 54.400 N	109° 18' 19.650 W	Circle (Radius: 25.00)

WELL DETAILS: Bonanza 1023-15I2AS

+N-S	+E-W	Northing	Ground Level:	5603.00	Latitude	Longitude	Slot
0.00	0.00	14511558.06	Easting	2115730.34	39° 56' 52.120 N	109° 18' 14.900 W	

LEGEND

- Bonanza 1023-15I4BS, Bonanza 1023-15I4BS, Bonanza 1023-15I4BS V0
- Bonanza 1023-15P1BS, Bonanza 1023-15P1BS, Bonanza 1023-15P1BS V0
- SWD #3 EXISTING, SWD #3 EXISTING, SWD #3 EXISTING V0
- Bonanza 1023-15H4CS, Bonanza 1023-15H4CS, Bonanza 1023-15H4CS V0
- BONANZA 1023-15H EXISTING, BONANZA 1023-15H EXISTING, BONANZA 1023-15H EXISTING V0
- Bonanza 1023-15I2AS, Bonanza 1023-15I2AS, PLAN #1 1-27-10 RHS V0
- Bonanza 1023-15I2AS
- WFT MWD SVY



Company: ANADARKO PETROLEUM CORP.
Project: UTAH COUNTY, UTAH (nad 27)
Site: BONANZA 1023-15I PAD
Well: Bonanza 1023-15I2AS
Wellbore: Bonanza 1023-15I2AS
Design: Bonanza 1023-15I2AS

Local Co-ordinate Reference: Well Bonanza 1023-15I2AS
TVD Reference: WELL @ 5617.00ft (Original Well Elev)
MD Reference: WELL @ 5617.00ft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.21 Single User Db

Project	UINTAH COUNTY, UTAH (nad 27),		
Map System:	Universal Transverse Mercator (US Survey Fee	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	Zone 12N (114 W to 108 W)		

Site		BONANZA 1023-15I PAD, SECTION 15 T10S R23E			
Site Position:		Northing:	14,511,552.63 ft	Latitude:	39° 56' 52.070 N
From:	Lat/Long	Easting:	2,115,710.97 ft	Longitude:	109° 18' 15.150 W
Position Uncertainty:	0.00 ft	Slot Radius:	in	Grid Convergence:	1.09 °

Well	Bonanza 1023-15I2AS					
Well Position	+N/-S	0.00 ft	Northing:	14,511,558.06 ft	Latitude:	39° 56' 52.120 N
	+E/-W	0.00 ft	Easting:	2,115,730.34 ft	Longitude:	109° 18' 14.900 W
Position Uncertainty		0.00 ft	Wellhead Elevation:	ft	Ground Level:	5,603.00 ft

Wellbore	Bonanza 1023-15I2AS				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	BGGM2009	3/19/2010	11.16	65.92	52,461

Design	Bonanza 1023-15I2AS				
Audit Notes:					
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W	Direction	
	(ft)	(ft)	(ft)	(°)	
	0.00	0.00	0.00	310.36	

Survey Program	Date 3/24/2010				
From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description	
279.00	1,899.00	SCIENTIFIC MWD (Bonanza 1023-15I2AS)	MWD	MWD - Standard	
1,960.00	8,010.00	WFT MWD SVY (Bonanza 1023-15I2AS)	MWD	MWD - Standard	

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
279.00	0.34	61.49	279.00	0.40	0.73	-0.30	0.12	0.12	0.00
369.00	0.38	339.60	369.00	0.80	0.86	-0.13	0.53	0.04	-90.99
459.00	1.03	290.46	458.99	1.36	0.00	0.89	0.93	0.72	-54.60
549.00	2.31	291.71	548.95	2.32	-2.45	3.37	1.42	1.42	1.39
639.00	2.62	310.99	638.87	4.34	-5.68	7.14	0.98	0.34	21.42
729.00	2.73	309.04	728.77	7.04	-8.90	11.34	0.16	0.12	-2.17
819.00	2.52	313.21	818.68	9.74	-12.01	15.46	0.32	-0.23	4.63
909.00	2.74	314.68	908.58	12.61	-14.98	19.58	0.26	0.24	1.63
999.00	2.45	323.25	998.49	15.66	-17.66	23.60	0.54	-0.32	9.52
1,089.00	2.58	322.21	1,088.40	18.81	-20.05	27.46	0.15	0.14	-1.16
1,179.00	2.37	326.26	1,178.32	21.95	-22.33	31.23	0.30	-0.23	4.50

Company: ANADARKO PETROLEUM CORP.
Project: UINTAH COUNTY, UTAH (nad 27)
Site: BONANZA 1023-15I PAD
Well: Bonanza 1023-15I2AS
Wellbore: Bonanza 1023-15I2AS
Design: Bonanza 1023-15I2AS

Local Co-ordinate Reference: Well Bonanza 1023-15I2AS
TVD Reference: WELL @ 5617.00ft (Original Well Elev)
MD Reference: WELL @ 5617.00ft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.21 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
1,269.00	2.84	317.52	1,268.23	25.15	-24.87	35.23	0.68	0.52	-9.71
1,359.00	2.83	312.88	1,358.12	28.30	-28.00	39.67	0.26	-0.01	-5.16
1,449.00	3.15	299.28	1,447.99	31.02	-31.79	44.31	0.86	0.36	-15.11
1,539.00	3.05	294.15	1,537.86	33.21	-36.13	49.04	0.33	-0.11	-5.70
1,629.00	2.98	294.17	1,627.74	35.15	-40.45	53.58	0.08	-0.08	0.02
1,719.00	2.50	314.19	1,717.64	37.48	-43.99	57.79	1.18	-0.53	22.24
1,809.00	2.64	310.85	1,807.55	40.20	-46.96	61.82	0.23	0.16	-3.71
TIE-IN SDI MWD SVY									
1,899.00	2.46	303.33	1,897.46	42.62	-50.15	65.81	0.42	-0.20	-8.36
BEGIN WFT MWD SVY									
1,960.00	2.74	303.70	1,958.39	44.15	-52.45	68.56	0.46	0.46	0.61
2,051.00	4.63	298.17	2,049.20	47.09	-57.50	74.31	2.11	2.08	-6.08
2,141.00	6.88	300.92	2,138.74	51.57	-65.33	83.18	2.52	2.50	3.06
2,232.00	9.63	302.55	2,228.79	58.47	-76.42	96.10	3.03	3.02	1.79
2,321.00	11.25	305.55	2,316.32	67.52	-89.76	112.12	1.92	1.82	3.37
2,413.00	13.11	303.20	2,406.24	78.45	-105.80	131.42	2.09	2.02	-2.55
2,504.00	15.38	305.67	2,494.44	91.14	-124.24	153.69	2.58	2.49	2.71
2,595.00	18.81	306.55	2,581.41	106.92	-145.83	180.36	3.78	3.77	0.97
2,686.00	20.75	308.05	2,667.03	125.60	-170.31	211.11	2.20	2.13	1.65
2,776.00	22.25	305.17	2,750.77	145.24	-196.80	244.01	2.04	1.67	-3.20
2,867.00	23.05	300.49	2,834.76	164.20	-226.24	278.73	2.17	0.88	-5.14
2,958.00	20.56	291.67	2,919.26	179.15	-256.45	311.43	4.52	-2.74	-9.69
3,048.00	17.75	289.17	3,004.27	189.49	-284.10	339.20	3.25	-3.12	-2.78
3,139.00	14.56	289.17	3,091.67	197.81	-308.01	362.80	3.51	-3.51	0.00
3,230.00	12.38	292.42	3,180.16	205.28	-327.84	382.75	2.54	-2.40	3.57
3,320.00	10.54	293.55	3,268.36	212.25	-344.31	399.81	2.06	-2.04	1.26
3,411.00	9.19	296.55	3,358.02	218.83	-358.44	414.83	1.59	-1.48	3.30
3,502.00	6.88	306.55	3,448.12	225.32	-369.32	427.33	2.96	-2.54	10.99
3,592.00	3.69	307.80	3,537.73	230.31	-375.94	435.61	3.55	-3.54	1.39
3,683.00	1.06	296.67	3,628.64	232.48	-379.00	439.35	2.92	-2.89	-12.23
3,773.00	1.19	288.30	3,718.62	233.15	-380.64	441.02	0.23	0.14	-9.30
3,864.00	1.25	355.05	3,809.61	234.43	-381.62	442.61	1.48	0.07	73.35
3,954.00	0.63	7.42	3,899.60	235.90	-381.64	443.57	0.72	-0.69	13.74
4,045.00	0.63	24.55	3,990.59	236.85	-381.37	443.98	0.21	0.00	18.82
4,136.00	1.88	23.92	4,081.57	238.67	-380.55	444.54	1.37	1.37	-0.69
4,226.00	1.88	31.17	4,171.52	241.29	-379.19	445.19	0.26	0.00	8.06
4,317.00	1.64	33.31	4,262.48	243.65	-377.70	445.59	0.27	-0.26	2.35
4,408.00	1.06	26.30	4,353.45	245.49	-376.62	445.96	0.66	-0.64	-7.70
4,498.00	0.63	4.55	4,443.44	246.73	-376.21	446.45	0.59	-0.48	-24.17
4,589.00	0.44	21.80	4,534.44	247.56	-376.04	446.85	0.27	-0.21	18.96
4,679.00	0.25	45.80	4,624.43	248.01	-375.77	446.94	0.26	-0.21	26.67
4,770.00	0.26	39.11	4,715.43	248.31	-375.50	446.93	0.03	0.01	-7.35
4,861.00	0.38	99.80	4,806.43	248.42	-375.07	446.67	0.37	0.13	66.69
4,951.00	0.50	121.30	4,896.43	248.17	-374.44	446.03	0.22	0.13	23.89
5,042.00	0.44	139.09	4,987.43	247.70	-373.87	445.29	0.17	-0.07	19.55
5,133.00	0.56	167.17	5,078.42	247.00	-373.54	444.59	0.30	0.13	30.86
5,223.00	0.99	170.55	5,168.41	245.80	-373.32	443.64	0.48	0.48	3.76
5,314.00	0.75	248.92	5,259.41	244.81	-373.74	443.33	1.23	-0.26	86.12
5,405.00	0.81	227.55	5,350.40	244.16	-374.77	443.69	0.32	0.07	-23.48
5,495.00	0.81	218.30	5,440.39	243.24	-375.64	443.75	0.15	0.00	-10.28
5,586.00	1.06	198.92	5,531.38	241.94	-376.31	443.42	0.44	0.27	-21.30
5,677.00	1.20	188.92	5,622.36	240.20	-376.73	442.61	0.27	0.15	-10.99
5,767.00	1.31	267.30	5,712.34	239.22	-377.90	442.87	1.76	0.12	87.09
5,858.00	1.31	235.80	5,803.32	238.58	-379.80	443.91	0.78	0.00	-34.62

Company: ANADARKO PETROLEUM CORP.
Project: UTAH COUNTY, UTAH (nad 27)
Site: BONANZA 1023-15I PAD
Well: Bonanza 1023-15I2AS
Wellbore: Bonanza 1023-15I2AS
Design: Bonanza 1023-15I2AS

Local Co-ordinate Reference: Well Bonanza 1023-15I2AS
TVD Reference: WELL @ 5617.00ft (Original Well Elev)
MD Reference: WELL @ 5617.00ft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.21 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
5,949.00	1.31	223.05	5,894.30	237.24	-381.37	444.24	0.32	0.00	-14.01
6,040.00	1.31	205.92	5,985.27	235.54	-382.54	444.03	0.43	0.00	-18.82
6,130.00	1.40	185.60	6,075.25	233.52	-383.10	443.14	0.54	0.10	-22.58
6,221.00	0.00	271.80	6,166.24	232.42	-383.20	442.51	1.54	-1.54	0.00
6,311.00	1.50	69.55	6,256.23	232.83	-382.10	441.94	1.67	1.67	0.00
6,402.00	1.56	101.42	6,347.20	233.00	-379.77	440.27	0.93	0.07	35.02
6,493.00	1.88	106.67	6,438.16	232.33	-377.13	437.82	0.39	0.35	5.77
6,583.00	0.31	306.80	6,528.14	232.05	-375.91	436.71	2.42	-1.74	-177.63
6,674.00	0.31	149.17	6,619.14	231.99	-375.98	436.72	0.67	0.00	-173.22
6,764.00	0.50	127.30	6,709.14	231.54	-375.54	436.10	0.27	0.21	-24.30
6,855.00	0.63	120.55	6,800.14	231.04	-374.79	435.21	0.16	0.14	-7.42
6,946.00	0.94	133.80	6,891.13	230.27	-373.82	433.97	0.39	0.34	14.56
7,036.00	0.75	136.42	6,981.12	229.33	-372.89	432.65	0.22	-0.21	2.91
7,127.00	1.21	138.33	7,072.11	228.19	-371.84	431.11	0.51	0.51	2.10
7,218.00	1.44	115.92	7,163.08	226.97	-370.17	429.05	0.62	0.25	-24.63
7,308.00	1.63	123.05	7,253.05	225.78	-368.08	426.68	0.30	0.21	7.92
7,399.00	1.75	90.30	7,344.01	225.06	-365.60	424.34	1.05	0.13	-35.99
7,490.00	0.63	92.42	7,434.99	225.03	-363.72	422.88	1.23	-1.23	2.33
7,580.00	0.90	101.17	7,524.98	224.88	-362.53	421.87	0.33	0.30	9.72
7,671.00	0.69	111.92	7,615.97	224.53	-361.32	420.73	0.28	-0.23	11.81
7,762.00	1.06	120.05	7,706.96	223.91	-360.08	419.38	0.43	0.41	8.93
7,853.00	1.19	137.42	7,797.95	222.79	-358.71	417.61	0.40	0.14	19.09
7,943.00	1.44	130.17	7,887.92	221.37	-357.22	415.55	0.33	0.28	-8.06
LAST WFT MWD SVY									
7,960.00	1.62	134.27	7,904.92	221.07	-356.88	415.10	1.24	1.06	24.12
EXT. TD									
8,010.00	1.62	134.27	7,954.90	220.08	-355.87	413.69	0.00	0.00	0.00

Design Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment
		+N/-S (ft)	+E/-W (ft)	
1,899.00	1,897.46	42.62	-50.15	TIE-IN SDI MWD SVY
1,960.00	1,958.39	44.15	-52.45	BEGIN WFT MWD SVY
7,960.00	7,904.92	221.07	-356.88	LAST WFT MWD SVY
8,010.00	7,954.90	220.08	-355.87	EXT. TD

Checked By: _____ Approved By: _____ Date: _____



ANADARKO PETROLEUM CORP.

UINTAH COUNTY, UTAH (nad 27)

BONANZA 1023-15I PAD

Bonanza 1023-15I2AS

Bonanza 1023-15I2AS

Design: Bonanza 1023-15I2AS

Survey Report - Geographic

24 March, 2010



Company: ANADARKO PETROLEUM CORP.
Project: UINTAH COUNTY, UTAH (nad 27)
Site: BONANZA 1023-15I PAD
Well: Bonanza 1023-15I2AS
Wellbore: Bonanza 1023-15I2AS
Design: Bonanza 1023-15I2AS

Local Co-ordinate Reference: Well Bonanza 1023-15I2AS
TVD Reference: WELL @ 5617.00ft (Original Well Elev)
MD Reference: WELL @ 5617.00ft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.21 Single User Db

Project	UINTAH COUNTY, UTAH (nad 27),		
Map System:	Universal Transverse Mercator (US Survey Fee	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	Zone 12N (114 W to 108 W)		

Site	BONANZA 1023-15I PAD, SECTION 15 T10S R23E			
Site Position:		Northing:	14,511,552.63 ft	Latitude: 39° 56' 52.070 N
From:	Lat/Long	Easting:	2,115,710.97 ft	Longitude: 109° 18' 15.150 W
Position Uncertainty:	0.00 ft	Slot Radius:	in	Grid Convergence: 1.09 °

Well	Bonanza 1023-15I2AS			
Well Position	+N/-S	0.00 ft	Northing:	14,511,558.06 ft
	+E/-W	0.00 ft	Easting:	2,115,730.34 ft
Position Uncertainty	0.00 ft	Wellhead Elevation:	ft	Ground Level: 5,603.00 ft

Wellbore	Bonanza 1023-15I2AS				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	BGGM2009	3/19/2010	11.16	65.92	52,461

Design	Bonanza 1023-15I2AS				
Audit Notes:					
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)	
	0.00	0.00	0.00	310.36	

Survey Program	Date 3/24/2010				
From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description	
279.00	1,899.00	SCIENTIFIC MWD (Bonanza 1023-15I2AS)	MWD	MWD - Standard	
1,960.00	8,010.00	WFT MWD SVY (Bonanza 1023-15I2AS)	MWD	MWD - Standard	

Company: ANADARKO PETROLEUM CORP.
Project: UINTAH COUNTY, UTAH (nad 27)
Site: BONANZA 1023-15I PAD
Well: Bonanza 1023-15I2AS
Wellbore: Bonanza 1023-15I2AS
Design: Bonanza 1023-15I2AS

Local Co-ordinate Reference: Well Bonanza 1023-15I2AS
TVD Reference: WELL @ 5617.00ft (Original Well Elev)
MD Reference: WELL @ 5617.00ft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.21 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (ft)	Map Easting (ft)	Latitude	Longitude
0.00	0.00	0.00	0.00	0.00	0.00	14,511,558.06	2,115,730.34	39° 56' 52.120 N	109° 18' 14.900 W
279.00	0.34	61.49	279.00	0.40	0.73	14,511,558.47	2,115,731.06	39° 56' 52.124 N	109° 18' 14.891 W
369.00	0.38	339.60	369.00	0.80	0.86	14,511,558.88	2,115,731.18	39° 56' 52.128 N	109° 18' 14.889 W
459.00	1.03	290.46	458.99	1.36	0.00	14,511,559.42	2,115,730.31	39° 56' 52.133 N	109° 18' 14.900 W
549.00	2.31	291.71	548.95	2.32	-2.45	14,511,560.33	2,115,727.85	39° 56' 52.143 N	109° 18' 14.931 W
639.00	2.62	310.99	638.87	4.34	-5.68	14,511,562.29	2,115,724.57	39° 56' 52.163 N	109° 18' 14.973 W
729.00	2.73	309.04	728.77	7.04	-8.90	14,511,564.93	2,115,721.31	39° 56' 52.190 N	109° 18' 15.014 W
819.00	2.52	313.21	818.68	9.74	-12.01	14,511,567.57	2,115,718.15	39° 56' 52.216 N	109° 18' 15.054 W
909.00	2.74	314.68	908.58	12.61	-14.98	14,511,570.38	2,115,715.12	39° 56' 52.245 N	109° 18' 15.092 W
999.00	2.45	323.25	998.49	15.66	-17.66	14,511,573.38	2,115,712.39	39° 56' 52.275 N	109° 18' 15.127 W
1,089.00	2.58	322.21	1,088.40	18.81	-20.05	14,511,576.48	2,115,709.93	39° 56' 52.306 N	109° 18' 15.158 W
1,179.00	2.37	326.26	1,178.32	21.95	-22.33	14,511,579.58	2,115,707.60	39° 56' 52.337 N	109° 18' 15.187 W
1,269.00	2.84	317.52	1,268.23	25.15	-24.87	14,511,582.73	2,115,705.00	39° 56' 52.369 N	109° 18' 15.219 W
1,359.00	2.83	312.88	1,358.12	28.30	-28.00	14,511,585.82	2,115,701.81	39° 56' 52.400 N	109° 18' 15.260 W
1,449.00	3.15	299.28	1,447.99	31.02	-31.79	14,511,588.47	2,115,697.97	39° 56' 52.427 N	109° 18' 15.308 W
1,539.00	3.05	294.15	1,537.86	33.21	-36.13	14,511,590.58	2,115,693.59	39° 56' 52.448 N	109° 18' 15.364 W
1,629.00	2.98	294.17	1,627.74	35.15	-40.45	14,511,592.43	2,115,689.23	39° 56' 52.467 N	109° 18' 15.419 W
1,719.00	2.50	314.19	1,717.64	37.48	-43.99	14,511,594.69	2,115,685.65	39° 56' 52.490 N	109° 18' 15.465 W
1,809.00	2.64	310.85	1,807.55	40.20	-46.96	14,511,597.36	2,115,682.62	39° 56' 52.517 N	109° 18' 15.503 W
TIE-IN SDI MWD SVY									
1,899.00	2.46	303.33	1,897.46	42.62	-50.15	14,511,599.71	2,115,679.39	39° 56' 52.541 N	109° 18' 15.544 W
BEGIN WFT MWD SVY									
1,960.00	2.74	303.70	1,958.39	44.15	-52.45	14,511,601.20	2,115,677.06	39° 56' 52.556 N	109° 18' 15.574 W
2,051.00	4.63	298.17	2,049.20	47.09	-57.50	14,511,604.04	2,115,671.96	39° 56' 52.585 N	109° 18' 15.638 W
2,141.00	6.88	300.92	2,138.74	51.57	-65.33	14,511,608.38	2,115,664.04	39° 56' 52.630 N	109° 18' 15.739 W
2,232.00	9.63	302.55	2,228.79	58.47	-76.42	14,511,615.06	2,115,652.82	39° 56' 52.698 N	109° 18' 15.881 W
2,321.00	11.25	305.55	2,316.32	67.52	-89.76	14,511,623.86	2,115,639.31	39° 56' 52.787 N	109° 18' 16.053 W
2,413.00	13.11	303.20	2,406.24	78.45	-105.80	14,511,634.49	2,115,623.07	39° 56' 52.895 N	109° 18' 16.259 W
2,504.00	15.38	305.67	2,494.44	91.14	-124.24	14,511,646.82	2,115,604.39	39° 56' 53.021 N	109° 18' 16.495 W
2,595.00	18.81	306.55	2,581.41	106.92	-145.83	14,511,662.19	2,115,582.50	39° 56' 53.177 N	109° 18' 16.773 W
2,686.00	20.75	308.05	2,667.03	125.60	-170.31	14,511,680.39	2,115,557.67	39° 56' 53.361 N	109° 18' 17.087 W
2,776.00	22.25	305.17	2,750.77	145.24	-196.80	14,511,699.53	2,115,530.82	39° 56' 53.556 N	109° 18' 17.427 W
2,867.00	23.05	300.49	2,834.76	164.20	-226.24	14,511,717.93	2,115,501.02	39° 56' 53.743 N	109° 18' 17.805 W
2,958.00	20.56	291.67	2,919.26	179.15	-256.45	14,511,732.30	2,115,470.53	39° 56' 53.891 N	109° 18' 18.193 W
3,048.00	17.75	289.17	3,004.27	189.49	-284.10	14,511,742.12	2,115,442.69	39° 56' 53.993 N	109° 18' 18.548 W
3,139.00	14.56	289.17	3,091.67	197.81	-308.01	14,511,749.97	2,115,418.62	39° 56' 54.075 N	109° 18' 18.855 W
3,230.00	12.38	292.42	3,180.16	205.28	-327.84	14,511,757.07	2,115,398.66	39° 56' 54.149 N	109° 18' 19.110 W
3,320.00	10.54	293.55	3,268.36	212.25	-344.31	14,511,763.73	2,115,382.06	39° 56' 54.218 N	109° 18' 19.321 W
3,411.00	9.19	296.55	3,358.02	218.83	-358.44	14,511,770.03	2,115,367.81	39° 56' 54.283 N	109° 18' 19.503 W
3,502.00	6.88	306.55	3,448.12	225.32	-369.32	14,511,776.32	2,115,356.81	39° 56' 54.347 N	109° 18' 19.643 W
3,592.00	3.69	307.80	3,537.73	230.31	-375.94	14,511,781.18	2,115,350.09	39° 56' 54.396 N	109° 18' 19.728 W
3,683.00	1.06	296.67	3,628.64	232.48	-379.00	14,511,783.29	2,115,346.99	39° 56' 54.418 N	109° 18' 19.767 W
3,773.00	1.19	288.30	3,718.62	233.15	-380.64	14,511,783.93	2,115,345.34	39° 56' 54.424 N	109° 18' 19.788 W
3,864.00	1.25	355.05	3,809.61	234.43	-381.62	14,511,785.19	2,115,344.34	39° 56' 54.437 N	109° 18' 19.801 W
3,954.00	0.63	7.42	3,899.60	235.90	-381.64	14,511,786.66	2,115,344.29	39° 56' 54.452 N	109° 18' 19.801 W
4,045.00	0.63	24.55	3,990.59	236.85	-381.37	14,511,787.62	2,115,344.54	39° 56' 54.461 N	109° 18' 19.797 W
4,136.00	1.88	23.92	4,081.57	238.67	-380.55	14,511,789.45	2,115,345.32	39° 56' 54.479 N	109° 18' 19.787 W
4,226.00	1.88	31.17	4,171.52	241.29	-379.19	14,511,792.09	2,115,346.63	39° 56' 54.505 N	109° 18' 19.769 W
4,317.00	1.64	33.31	4,262.48	243.65	-377.70	14,511,794.48	2,115,348.08	39° 56' 54.528 N	109° 18' 19.750 W
4,408.00	1.06	26.30	4,353.45	245.49	-376.62	14,511,796.35	2,115,349.13	39° 56' 54.546 N	109° 18' 19.736 W
4,498.00	0.63	4.55	4,443.44	246.73	-376.21	14,511,797.60	2,115,349.51	39° 56' 54.559 N	109° 18' 19.731 W
4,589.00	0.44	21.80	4,534.44	247.56	-376.04	14,511,798.42	2,115,349.67	39° 56' 54.567 N	109° 18' 19.729 W
4,679.00	0.25	45.80	4,624.43	248.01	-375.77	14,511,798.88	2,115,349.93	39° 56' 54.571 N	109° 18' 19.725 W
4,770.00	0.26	39.11	4,715.43	248.31	-375.50	14,511,799.19	2,115,350.19	39° 56' 54.574 N	109° 18' 19.722 W
4,861.00	0.38	99.80	4,806.43	248.42	-375.07	14,511,799.30	2,115,350.62	39° 56' 54.575 N	109° 18' 19.716 W

Company: ANADARKO PETROLEUM CORP.
Project: UINTAH COUNTY, UTAH (nad 27)
Site: BONANZA 1023-15I PAD
Well: Bonanza 1023-15I2AS
Wellbore: Bonanza 1023-15I2AS
Design: Bonanza 1023-15I2AS

Local Co-ordinate Reference: Well Bonanza 1023-15I2AS
TVD Reference: WELL @ 5617.00ft (Original Well Elev)
MD Reference: WELL @ 5617.00ft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.21 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (ft)	Map Easting (ft)	Latitude	Longitude
4,951.00	0.50	121.30	4,896.43	248.17	-374.44	14,511,799.06	2,115,351.25	39° 56' 54.573 N	109° 18' 19.708 W
5,042.00	0.44	139.09	4,987.43	247.70	-373.87	14,511,798.60	2,115,351.83	39° 56' 54.568 N	109° 18' 19.701 W
5,133.00	0.56	167.17	5,078.42	247.00	-373.54	14,511,797.91	2,115,352.17	39° 56' 54.561 N	109° 18' 19.697 W
5,223.00	0.99	170.55	5,168.41	245.80	-373.32	14,511,796.72	2,115,352.42	39° 56' 54.549 N	109° 18' 19.694 W
5,314.00	0.75	248.92	5,259.41	244.81	-373.74	14,511,795.72	2,115,352.01	39° 56' 54.540 N	109° 18' 19.699 W
5,405.00	0.81	227.55	5,350.40	244.16	-374.77	14,511,795.05	2,115,350.99	39° 56' 54.533 N	109° 18' 19.713 W
5,495.00	0.81	218.30	5,440.39	243.24	-375.64	14,511,794.11	2,115,350.15	39° 56' 54.524 N	109° 18' 19.724 W
5,586.00	1.06	198.92	5,531.38	241.94	-376.31	14,511,792.80	2,115,349.50	39° 56' 54.511 N	109° 18' 19.732 W
5,677.00	1.20	188.92	5,622.36	240.20	-376.73	14,511,791.05	2,115,349.11	39° 56' 54.494 N	109° 18' 19.738 W
5,767.00	1.31	267.30	5,712.34	239.22	-377.90	14,511,790.05	2,115,347.96	39° 56' 54.484 N	109° 18' 19.753 W
5,858.00	1.31	235.80	5,803.32	238.58	-379.80	14,511,789.38	2,115,346.07	39° 56' 54.478 N	109° 18' 19.777 W
5,949.00	1.31	223.05	5,894.30	237.24	-381.37	14,511,788.01	2,115,344.53	39° 56' 54.465 N	109° 18' 19.797 W
6,040.00	1.31	205.92	5,985.27	235.54	-382.54	14,511,786.29	2,115,343.39	39° 56' 54.448 N	109° 18' 19.812 W
6,130.00	1.40	185.60	6,075.25	233.52	-383.10	14,511,784.26	2,115,342.88	39° 56' 54.428 N	109° 18' 19.820 W
6,221.00	0.00	271.80	6,166.24	232.42	-383.20	14,511,783.15	2,115,342.79	39° 56' 54.417 N	109° 18' 19.821 W
6,311.00	1.50	69.55	6,256.23	232.83	-382.10	14,511,783.58	2,115,343.88	39° 56' 54.421 N	109° 18' 19.807 W
6,402.00	1.56	101.42	6,347.20	233.00	-379.77	14,511,783.80	2,115,346.21	39° 56' 54.423 N	109° 18' 19.777 W
6,493.00	1.88	106.67	6,438.16	232.33	-377.13	14,511,783.17	2,115,348.87	39° 56' 54.416 N	109° 18' 19.743 W
6,583.00	0.31	306.80	6,528.14	232.05	-375.91	14,511,782.92	2,115,350.09	39° 56' 54.414 N	109° 18' 19.727 W
6,674.00	0.31	149.17	6,619.14	231.99	-375.98	14,511,782.85	2,115,350.02	39° 56' 54.413 N	109° 18' 19.728 W
6,764.00	0.50	127.30	6,709.14	231.54	-375.54	14,511,782.42	2,115,350.47	39° 56' 54.408 N	109° 18' 19.722 W
6,855.00	0.63	120.55	6,800.14	231.04	-374.79	14,511,781.94	2,115,351.22	39° 56' 54.404 N	109° 18' 19.713 W
6,946.00	0.94	133.80	6,891.13	230.27	-373.82	14,511,781.18	2,115,352.21	39° 56' 54.396 N	109° 18' 19.700 W
7,036.00	0.75	136.42	6,981.12	229.33	-372.89	14,511,780.26	2,115,353.16	39° 56' 54.387 N	109° 18' 19.688 W
7,127.00	1.21	138.33	7,072.11	228.19	-371.84	14,511,779.13	2,115,354.24	39° 56' 54.375 N	109° 18' 19.675 W
7,218.00	1.44	115.92	7,163.08	226.97	-370.17	14,511,777.95	2,115,355.93	39° 56' 54.363 N	109° 18' 19.654 W
7,308.00	1.63	123.05	7,253.05	225.78	-368.08	14,511,776.80	2,115,358.04	39° 56' 54.352 N	109° 18' 19.627 W
7,399.00	1.75	90.30	7,344.01	225.06	-365.60	14,511,776.13	2,115,360.53	39° 56' 54.344 N	109° 18' 19.595 W
7,490.00	0.63	92.42	7,434.99	225.03	-363.72	14,511,776.14	2,115,362.42	39° 56' 54.344 N	109° 18' 19.571 W
7,580.00	0.90	101.17	7,524.98	224.88	-362.53	14,511,776.00	2,115,363.61	39° 56' 54.343 N	109° 18' 19.555 W
7,671.00	0.69	111.92	7,615.97	224.53	-361.32	14,511,775.68	2,115,364.82	39° 56' 54.339 N	109° 18' 19.540 W
7,762.00	1.06	120.05	7,706.96	223.91	-360.08	14,511,775.08	2,115,366.07	39° 56' 54.333 N	109° 18' 19.524 W
7,853.00	1.19	137.42	7,797.95	222.79	-358.71	14,511,773.99	2,115,367.46	39° 56' 54.322 N	109° 18' 19.506 W
7,943.00	1.44	130.17	7,887.92	221.37	-357.22	14,511,772.60	2,115,368.98	39° 56' 54.308 N	109° 18' 19.487 W
LAST WFT MWD SVY									
7,960.00	1.62	134.27	7,904.92	221.07	-356.88	14,511,772.30	2,115,369.32	39° 56' 54.305 N	109° 18' 19.483 W
EXT. TD									
8,010.00	1.62	134.27	7,954.90	220.08	-355.87	14,511,771.33	2,115,370.35	39° 56' 54.295 N	109° 18' 19.470 W

Company: ANADARKO PETROLEUM CORP.
Project: UINTAH COUNTY, UTAH (nad 27)
Site: BONANZA 1023-15I PAD
Well: Bonanza 1023-15I2AS
Wellbore: Bonanza 1023-15I2AS
Design: Bonanza 1023-15I2AS

Local Co-ordinate Reference: Well Bonanza 1023-15I2AS
TVD Reference: WELL @ 5617.00ft (Original Well Elev)
MD Reference: WELL @ 5617.00ft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.21 Single User Db

Design Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment
		+N/-S (ft)	+E/-W (ft)	
1,899.00	1,897.46	42.62	-50.15	TIE-IN SDI MWD SVY
1,960.00	1,958.39	44.15	-52.45	BEGIN WFT MWD SVY
7,960.00	7,904.92	221.07	-356.88	LAST WFT MWD SVY
8,010.00	7,954.90	220.08	-355.87	EXT. TD

Checked By: _____ Approved By: _____ Date: _____

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU 38427
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: BONANZA 1023-1512AS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2199 FSL 0339 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESE Section: 15 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047507420000
PHONE NUMBER: 720 929-6515 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA


TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 3/9/2011 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input checked="" type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER:

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The operator requests approval to conduct wellhead/casing repair operations on the subject well location. Please find the attached procedures for the proposed repair work on the subject well location.

Accepted by the
Utah Division of
Oil, Gas and Mining

Date: 03/10/2011

By: 

NAME (PLEASE PRINT) Gina Becker	PHONE NUMBER 720 929-6086	TITLE Regulatory Analyst II
SIGNATURE N/A		DATE 3/9/2011

WORKORDER #: 88119298

Name: **BONANZA 1023-15I2AS - 1023-15I PAD**
Surface Location: NESE SEC.15 T10S, R23E
Uintah County, UT

3/4/11

API: 4304750742 LEASE#: UTU-38427

ELEVATIONS: 5603' GL 5617' KB

TOTAL DEPTH: 8010' PBTD: 7955'

SURFACE CASING: 8 5/8", 28# J-55 @ 1915'

PRODUCTION CASING: 4 1/2", 11.6#, I-80 @ 8000'
T.O.C.@ 108 per CBL

PERFORATIONS: Mesaverde 6414' - 7787'

Tubular/Borehole	Drift inches	Collapse psi	Burst psi	Capacities		
				Gal./ft.	Cuft/ft.	Bbl./ft.
2.375" 4.7# J-55 tbg.	1.901	8100	7700	0.1624	0.02173	0.00387
4.5" 11.6# I-80	3.875	6350	7780	0.6528	0.0872	0.01554
8.625" 28# J-55	8.097	1370	2950	2.6223	0.3505	0.0624
Annular Capacities						
2.375" tbg. X 4 1/2" 11.6# csg				0.4227	0.0565	0.01006

GEOLOGICAL TOPS:

974' Green River
1215' Bird's Nest
1803' Mahogany
4035' Wasatch
5803' Mesaverde

BONANZA 1023-15I2AS – WELLHEAD REPLACEMENT PROCEDURE

PREP-WORK PRIOR TO MIRU:

1. Dig out down to the 2" surface casing valve or to the valve on the riser off the surface casing.
2. Install a tee with 2 valves, with a pressure gauge and sensor on one valve.
3. Open casing valve and record pressures.
4. Install nipple and steel hose on the other valve, the relief valve,. Do not use hammer unions. No impact equipment or tools to be used for any of this installation. Extend hose and hard piping to a downwind location at least 100' from the wellhead. Consider installing a manifold so that vent area could be in two locations approx. 90 degrees apart from the wellhead.
5. Open the relief valve and blow well down to the atmosphere.
6. Make a determination of amount of gas flow, either by installation of a choke nipple, bucket test or other.
7. Shut well in. Observe for rate of build-up by utilizing sensor data. Do not build-up for more than 24 hours. Vent gas through the vent line and leave open to the atmosphere.

WORKOVER PROCEDURE:

1. MIRU workover rig.
2. Kill well with 10# brine / KCL (dictated by well pressure).
3. Remove tree, install double BOP with blind and 2 3/8" pipe rams, with accumulator closing unit and manual back-ups. Function test BOP system.
4. Pooh w/ tubing.
5. Rig up wireline service. RIH and set CBP @ ~6364'. Dump bail 4 sx cement on top of plug. POOH and RD wireline service.
6. Remove BOP and ND WH.
7. Depending on conditions at wellsite, continue with either CUT/PATCH Procedure or BACK-OFF Procedure.

CUT/PATCH PROCEDURE:

1. PU internal casing cutters and RIH. Cut casing at +/- 30' from surface.
2. POOH, LD cutters and casing.
3. PU 1 joint of 3 ½" IF drill pipe with 4 ½" right hand standard grapple overshot. Pull a minimum of 10,000# to keep grapple engaged if cement top is high (<~900'). If cement top is low (>~900'), more weight will be required to put casing in neutral. Torque casing string to +/- 7000 ft-lbs, count number of turns to make-up, and document in the daily report. Release overshot, POOH, and lay down.
4. PU & RIH w/ 4 ½" 10k external casing patch on 4 ½" I-80 or P-110 casing.
5. Latch fish, PU to 100,000# tension. RU B&C. Cycle pressure test to 7,000# / 9,000# psi.
6. Install C-22 slips. Land casing w/ 80,000# tension.
7. Cut-off and dress 4 ½" casing stub.
8. NUWH. PU 3 7/8" bit, POBS and RIH. D/O cement and plug ~6314'. Clean out to PBTD (7955').
9. POOH, land tbg and pump off POBS.
10. NUWH, RDMO. Turn well over to production ops.

BACK-OFF PROCEDURE:

1. PU internal casing cutters and RIH. Cut casing at +/- 6' from surface.
2. POOH, LD cutters and casing.
3. PU 4 ½" overshot. RIH, latch fish. Pick string weight to neutral.
4. MIRU wireline services. RIH and shoot string shot at casing collar @ 46'.
5. MIRU casing crew.
6. Back-off casing, POOH.
7. PU new casing joint w/ entry guide and RIH. Tag casing top. Thread into casing and torque up to +/- 7000 ft-lbs, count number of additional turns to make-up, and document in the daily report.
8. PU 100,000# tension string weight. RU B&C. Cycle pressure test to 7,000# / 9,000# psi.
9. Install C-22 slips. Land casing w/ 80,000# tension.

10. Cut-off and dress 4 ½" casing stub.
11. NUWH. PU 3 7/8" bit, POBS and RIH. D/O cement and plug ~6314'. Clean out to PBTD (7955').
12. POOH, land tbg and pump off POBS.
13. NUWH, RDMO. Turn well over to production ops.




Logan High Pressure Casing Patches Assembly Procedure

All parts should be thoroughly greased before being assembled.


1. Install all four Logan Type "L" Packers in the spaces provided in the Casing Patch Bowl. Refer to diagram provided for proper installation.
2. Install Packer Protector from the Basket Grapple end of the Bowl. The beveled end of the Packer Protector goes in first. Carefully push the Packer Protector through the four Type "L" Packers.
3. Align Shear Pin Holes in Packer Protector so that the holes have just passed into the counter bore at the Top Sub end, refer to diagram. The Packer Protector is provided with four Shear Pin Holes. Use only two holes, 180 degrees apart and install the pins.
4. Screw the Basket Grapple in from the lower end of the Bowl, using left-hand rotation. The Tang Slot in the Basket Grapple must land in line with the slot in the Bowl.
5. Insert the Basket Grapple Control into the end of the Bowl. Align Tang on the Basket Grapple Control with the Tang Slot of the Bowl and Basket Grapple. This secures the Bowl and the Basket Grapple together.
6. Install the Cutlipped Guide into the lower end of the Bowl.
7. Install O-Rings on the two five-foot long Extensions. Screw the first Extension into the top end of the Bowl. Screw the second Extension into the top end of the first Extension.
8. Install O-Ring on Top Sub. Screw Top Sub into top end of second Extension.

Follow recommended Make-Up Torque as provided in chart.

510L-005-001 4-1/2" LOGAN HP CASING PATCH



**STRENGTH DATA FOR LOGAN 5.88" OD "L" TYPE CSG PATCH
4-1/2 CASING, 10K PSI MAX WP 125K YIELD MAT'L
LOGAN ASSEMBLY NO. 510L-005 -000**



COLLAPSE PRESSURE:
11,222 PSI @ 0 TENSILE
8,634 PSI @ 220K TENSILE

Tensile Strength @ Yield:
Tensile Strength w/ 0 Int. Press.= 472,791lbs.
Tensile Strength w/ 10K Int. Press.= 313,748lbs.

DATA BY SLS 11/16/2009

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU 38427
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: BONANZA 1023-1512AS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2199 FSL 0339 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESE Section: 15 Township: 10.0S Range: 23.0E Meridian: S		9. API NUMBER: 43047507420000
PHONE NUMBER: 720 929-6515 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input checked="" type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> APD EXTENSION <input type="checkbox"/> WILDCAT WELL DETERMINATION <input checked="" type="checkbox"/> OTHER	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 5/9/2011	OTHER: <input style="width: 100px;" type="text" value="Wellhead Repair"/>	
<input type="checkbox"/> SPUD REPORT Date of Spud:		
<input type="checkbox"/> DRILLING REPORT Report Date:		
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The operator has concluded wellhead/casing repairs on the subject well location. Please see the attached chronological history for details of the operations.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY		
NAME (PLEASE PRINT) Gina Becker	PHONE NUMBER 720 929-6086	TITLE Regulatory Analyst II
SIGNATURE N/A	DATE 5/9/2011	

US ROCKIES REGION

Operation Summary Report

Well: BONANZA 1023-15I2AS (YELLOW)			Spud Conductor: 1/31/2010			Spud Date: 2/7/2010			
Project: UTAH-UINTAH			Site: BONANZA 1023-15I PAD				Rig Name No: LEED 698/698		
Event: WELL WORK EXPENSE			Start Date: 3/25/2011				End Date: 3/29/2011		
Active Datum: DFE @0.00ft (above Mean Sea Level)			UWI: NE/SE/0/10/S/23/E/15/0/0/6/PM/S/2,199.00/E/0/339.00/0/0						
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation	
3/22/2011	7:00 -		PROD	35	G	P		Travel to location rig up went in with G1 tool stacked o at 7291 beat down latch on plunger came out had a bypass viper plunger went back in latch on spring hit o jars 6 broke loose came out had a titanium spring rig down travel to next location.LEFT PLUNGER AND SPRING OUT FOR WORKOVER. FLUID LEVEL 6600SEAT NIPPLE DEPTH 7291 SN TYPE X TD (Max Depth) 7291 JOB DETAILS SPRING AND/OR PRODUCTION TOOL DETAIL Spring Out Used-Titanium Spring In Used-Titanium Stuck Spring Yes, stuck but able to latch on Corrosion on SpringNo Bailed Acid No Broken Spring No Scale on Spring Yes Production Tools None Depth of Tool Other Hardware None PLUNGER DETAIL Stuck Plunger Yes, stuck but able to latch on Corrosion on Plunger No Broken PlungerNo Scale on Plunger No SOLIDS DETAIL Tight Spots None Severity of Trash Light Solid sample to turn in Yes Solid Sample Source Tubing Speculated Type of Solid Iron Sulfide Speculated Depth of Solid LOST SLICKLINE TOOLS Slickline Tools Lost No Depth of Tool	
3/25/2011	9:00 - 9:30	0.50	ALL	48		P		HSM, RU & RD	
	9:30 - 10:30	1.00	ALL	30	A	P		MOVE RIG F/ BONANZA 1023-15P1BS TO BONANZA 1023-15I2AS, MIRU.	
	10:30 - 11:15	0.75	ALL	47	A	P		FCP. 312 PSI. SITP. 312 PSI. BLEW TBG, CONTROL TBG W/ 10 BBLs, ND WH, NU BOPS, RU FLOOR & TBG EQUIPMENT.	
	11:15 - 14:30	3.25	ALL	31	I	P		UNLAND TBG. POOH 231 JTS. 2-3/8 L-80 TBG, (REPAIR RADATOR IN RIG)	
	14:30 - 16:00	1.50	ALL	34	I	P		RU CUTTERS, RIH 3.625 GAUGE RING, POOH, RIH 4-1/2 10K CBP & SET @ 6365', POOH.	
	16:00 - 18:00	2.00	ALL	34	D	P		MADE 2 RUNS W/ BAILER & DUMP 4 SXS CLASS "G" CMT ON PLUG, RD CUTTERS, FILL 4-1/2 CSG W/ T-MAC, SWI, SDFWE.	
3/28/2011	7:00 - 7:30	0.50	ALL	48		P		HSM, REVIEW CUTTING 4-1/2 CSG.	
	7:30 - 7:45	0.25	ALL	30	F	P		ND BOPS, ND CSG HEAD.	
	7:45 - 8:00	0.25	ALL	47	A	P		RU PWR SWVL.	

US ROCKIES REGION

Operation Summary Report

Well: BONANZA 1023-1512AS (YELLOW)	Spud Conductor: 1/31/2010	Spud Date: 2/7/2010
Project: UTAH-UINTAH	Site: BONANZA 1023-151 PAD	Rig Name No: LEED 698/698
Event: WELL WORK EXPENSE	Start Date: 3/25/2011	End Date: 3/29/2011
Active Datum: DFE @0.00ft (above Mean Sea Level) UWI: NE/SE/0/10/S/23/E/15/0/0/6/PM/S/2,199.00/E/0/339.00/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	8:00 - 10:00	2.00	ALL	31	B	P		PU INTERNAL CSG CUTTER & RIH CUT 4-1/2 CSG 7' F/ SURFACE. RD PWR SWVL. PU 4-1/2 OVERSHOT & RIH LATCH ON FISH, RU CSG CREW, BACK-OFF 1JNT. 4-1/2 CSG W/ COLLAR, LD CUT CSG, PU NEW CSG JNT. W/ ENTRY GUIDE & RIH TAG CSG TOP, THREAD INTO 4-1/2 CSG, TORQUE 4-1/2 CSG TO 7000# FT/LBS W/ 22 REVOLUTION, RD CSG CREW. PU 100,000# IN TENSION.
	10:00 - 14:00	4.00	ALL	33	C			RU B&C QUICK TESTING, P.T. 4-1/2 CSG TO 1000 PSI. FOR 15 MINS, 3500 PSI. FOR 15 MINS. & 7000 PSI. FOR 30 MINS, HELD, INSTALL C-21 SLIP, LAND 4-1/2 CSG W/ 85,000# IN TENSION. CUT-OFF & DRESS 4-1/2 CSG STUB, INSTALL "H" PLATE & RING, P.T. SURFACE CSG 200 PSI. FOR 15 MINS, LOST 110 PSI IN 15 MINS, 500 PSI. FOR 30 MINS, LOST 250 PSI. IN 30 MINS. RD B&C QUICK TEST, INSTALL FLANGE & CROSSOVER SPOOL.
	14:00 - 14:30	0.50	ALL	31	I	P		NU CSG HEAD & BOPS, RU FLOOR & TBG EQUIPMENT.
	14:30 - 16:30	2.00	ALL	31	I	P		PU 3-7/8 MILL, POBS W/ 1.875 XN & RIH 200 JTS. L-80 TBG, TAG CMT @ 6327', LD 4 JTS. SWI, SDFN.
3/29/2011	7:00 - 7:30	0.50	ALL	48		P		HSM, REVIEW AIR FOAM UNIT.
	7:30 - 8:00	0.50	ALL	31	I	P		RIH 4 JTS. 2-3/8 L-80 TBG, TAG CMT @ 6327'.
	8:00 - 8:30	0.50	ALL	47	A	P		RU PWR SWVL, INSTALL TSF, RU AIR FOAM UNIT,
	8:30 - 8:40	0.17	ALL	31	H	P		BROKE CIRC IN 10 MINS,
	8:40 - 9:10	0.50	ALL	44	A	P		D/O CMT F/ 6327' TO 6365' IN 15 MINS & D/O CBP IN 15 MINS. @ 6365', HAD 150 PSI INCREASE.
	9:10 - 9:30	0.33	ALL	31	I	P		KILL TBG, LD PWR SWVL, REMOVE TSF, RIH & PU 21 JTS. 2-3/8 L-80 TBG, TAG FILL @ 7903'.
	9:30 - 11:15	1.75	ALL	31	H	P		INSTALL TSF, RU PWR SWVL, BROKE CIR IN 40 MINS, C/O F/ 7903' TO 7937' TAG OLD POBS, CIRC HOLE CLEAN,
	11:15 - 14:00	2.75	ALL	31	I	P		RD PWR SWVL, POOH 2 JTS. REMOVE TSF, DROP BALL, PUMP-OFF BIT W/ 10 BBLS @ 900 PSI, LD 20 JTS. 2-3/8 L-80 ON TRAILER, LAND TBG HANGER, BROACH TBG TO SN, GOOD, RD FLOOR EQUIPMENT, ND BOPS, NUWH, RDMO. MOVE TO BONANZA 1023-1514BS.
TBG DETAIL								
KB-----13'								
HANGER-----83"								
231 JTS. L-80 TBG @-----7289.89'								
POBS XN 1.875-----2.20'								
EOT @-----7305.92'								
TOP PERF @ 6414'								
BTM PERF @ 7787'								
NEW PBD @ 7937'								

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: KERR MCGEE OIL & GAS ONSHORE LP Operator Account Number: N 2995
Address: P.O. Box 173779
city DENVER
state CO zip 80217 Phone Number: (720) 929-6029

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
See Atchmt	See Atchmt						
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
	99999	18519				5/11/2012	
Comments: Please see attachment with list of Wells in the Ponderosa Unit. <u>WSMVD</u> 5/30/2012							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

RECEIVED

MAY 21 2012

Div. of Oil, Gas & Mining

Cara Mahler

Name (Please Print)

Signature

REGULATORY ANALYST

Title

5/21/2012

Date

well_name	sec	tpw	rng	api	entity		lease	well	stat	qtr_qtr	bhl	surf	zone	a_stat	l_num	op_no
SOUTHMAN CANYON 31-3	31	090S	230E	4304734726	13717		1	GW	P	SENW		1	WSMVD	P	U-33433	N2995
SOUTHMAN CANYON 31-4	31	090S	230E	4304734727	13742		1	GW	S	SESW		1	WSMVD	S	UTU-33433	N2995
SOUTHMAN CYN 31-2X (RIG SKID)	31	090S	230E	4304734898	13755		1	GW	P	NWNW		1	WSMVD	P	U-33433	N2995
SOUTHMAN CYN 923-31J	31	090S	230E	4304735149	13994		1	GW	P	NWSE		1	MVRD	P	U-33433	N2995
SOUTHMAN CYN 923-31B	31	090S	230E	4304735150	13953		1	GW	P	NWNE		1	MVRD	P	U-33433	N2995
SOUTHMAN CYN 923-31P	31	090S	230E	4304735288	14037		1	GW	P	SESE		1	WSMVD	P	UTU-33433	N2995
SOUTHMAN CYN 923-31H	31	090S	230E	4304735336	14157		1	GW	P	SENE		1	WSMVD	P	U-33433	N2995
SOUTHMAN CYN 923-31O	31	090S	230E	4304737205	16827		1	GW	P	SWSE		1	MVRD	P	UTU-33433	N2995
SOUTHMAN CYN 923-31K	31	090S	230E	4304737206	16503		1	GW	P	NESW		1	WSMVD	P	UTU-33433	N2995
SOUTHMAN CYN 923-31G	31	090S	230E	4304737208	16313		1	GW	P	SWNE		1	WSMVD	P	UTU-33433	N2995
SOUTHMAN CYN 923-31E	31	090S	230E	4304737209	16521		1	GW	P	SWNW		1	WSMVD	P	UTU-33433	N2995
SOUTHMAN CYN 923-31A	31	090S	230E	4304737210	16472		1	GW	P	NENE		1	WSMVD	P	UTU-33433	N2995
SOUTHMAN CYN 923-31C	31	090S	230E	4304737227	16522		1	GW	P	NENW		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-1G	01	100S	230E	4304735512	14458		1	GW	P	SWNE		1	WSMVD	P	U-40736	N2995
BONANZA 1023-1A	01	100S	230E	4304735717	14526		1	GW	P	NENE		1	WSMVD	P	U-40736	N2995
BONANZA 1023-1E	01	100S	230E	4304735745	14524		1	GW	P	SWNW		1	WSMVD	P	U-40736	N2995
BONANZA 1023-1C	01	100S	230E	4304735754	14684		1	GW	P	NENW		1	MVRD	P	U-40736	N2995
BONANZA 1023-1K	01	100S	230E	4304735755	15403		1	GW	P	NESW		1	MVRD	P	U-38423	N2995
BONANZA 1023-1F	01	100S	230E	4304737379	16872		1	GW	P	SENW		1	MVRD	P	UTU-40736	N2995
BONANZA 1023-1B	01	100S	230E	4304737380	16733		1	GW	P	NWNE		1	MVRD	P	UTU-40736	N2995
BONANZA 1023-1D	01	100S	230E	4304737381	16873		1	GW	P	NWNW		1	MVRD	P	UTU-40736	N2995
BONANZA 1023-1H	01	100S	230E	4304737430	16901		1	GW	P	SENE		1	MVRD	P	UTU-40736	N2995
BONANZA 1023-1L	01	100S	230E	4304738300	16735		1	GW	P	NWSW		1	MVRD	P	UTU-38423	N2995
BONANZA 1023-1J	01	100S	230E	4304738302	16871		1	GW	P	NWSE		1	MVRD	P	UTU-40736	N2995
BONANZA 1023-1I	01	100S	230E	4304738810	16750		1	GW	P	NESE		1	MVRD	P	UTU-40736	N2995
BONANZA 1023-2E	02	100S	230E	4304735345	14085		3	GW	P	SWNW		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2C	02	100S	230E	4304735346	14084		3	GW	P	NENW		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2A	02	100S	230E	4304735347	14068		3	GW	P	NENE		3	MVRD	P	ML-47062	N2995
BONANZA 1023-2G	02	100S	230E	4304735661	14291		3	GW	P	SWNE		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2O	02	100S	230E	4304735662	14289		3	GW	P	SWSE		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2I	02	100S	230E	4304735663	14290		3	GW	S	NESE		3	WSMVD	S	ML-47062	N2995
BONANZA 1023-2MX	02	100S	230E	4304736092	14730		3	GW	P	SWSW		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2H	02	100S	230E	4304737093	16004		3	GW	P	SENE		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2D	02	100S	230E	4304737094	15460		3	GW	P	NWNW		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2B	02	100S	230E	4304737095	15783		3	GW	P	NWNE		3	MVRD	P	ML-47062	N2995
BONANZA 1023-2P	02	100S	230E	4304737223	15970		3	GW	P	SESE		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2N	02	100S	230E	4304737224	15887		3	GW	P	SESW		3	MVRD	P	ML-47062	N2995
BONANZA 1023-2L	02	100S	230E	4304737225	15833		3	GW	P	NWSW		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2F	02	100S	230E	4304737226	15386		3	GW	P	SENW		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2D-4	02	100S	230E	4304738761	16033		3	GW	P	NWNW		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2O-1	02	100S	230E	4304738762	16013		3	GW	P	SWSE		3	WSMVD	P	ML-47062	N2995
BONANZA 1023-2H3CS	02	100S	230E	4304750344	17426		3	GW	P	NWNE	D	3	MVRD	P	ML 47062	N2995
BONANZA 1023-2G3BS	02	100S	230E	4304750345	17428		3	GW	P	NWNE	D	3	MVRD	P	ML 47062	N2995
BONANZA 1023-2G2CS	02	100S	230E	4304750346	17429		3	GW	P	NWNE	D	3	MVRD	P	ML 47062	N2995
BONANZA 1023-2G1BS	02	100S	230E	4304750347	17427		3	GW	P	NWNE	D	3	MVRD	P	ML 47062	N2995

BONANZA 1023-2M1S	02	100S	230E	4304750379	17443		3	GW	P	SENW	D	3	MVRD	P	ML 47062	N2995
BONANZA 1023-2L2S	02	100S	230E	4304750380	17444		3	GW	P	SENW	D	3	MVRD	P	ML 47062	N2995
BONANZA 1023-2K4S	02	100S	230E	4304750381	17446		3	GW	P	SENW	D	3	MVRD	P	ML 47062	N2995
BONANZA 1023-2K1S	02	100S	230E	4304750382	17445		3	GW	P	SENW	D	3	WSMVD	P	ML 47062	N2995
BONANZA 4-6 ✱	04	100S	230E	4304734751	13841		1	GW	P	NESW		1	MNCS	P	UTU-33433	N2995
BONANZA 1023-4A	04	100S	230E	4304735360	14261		1	GW	P	NENE		1	WSMVD	P	U-33433	N2995
BONANZA 1023-4E	04	100S	230E	4304735392	14155		1	GW	P	SWNW		1	WSMVD	P	U-33433	N2995
BONANZA 1023-4C	04	100S	230E	4304735437	14252		1	GW	P	NENW		1	WSMVD	P	U-33433	N2995
BONANZA 1023-4M	04	100S	230E	4304735629	14930		1	GW	P	SWSW		1	WSMVD	P	U-33433	N2995
BONANZA 1023-4O	04	100S	230E	4304735688	15111		1	GW	P	SWSE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-4I	04	100S	230E	4304735689	14446		1	GW	P	NESE		1	MVRD	P	UTU-33433	N2995
BONANZA 1023-4G	04	100S	230E	4304735746	14445		1	GW	P	SWNE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-4D	04	100S	230E	4304737315	16352		1	GW	P	NWNW		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-4H	04	100S	230E	4304737317	16318		1	GW	P	SENE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-4B	04	100S	230E	4304737328	16351		1	GW	P	NWNE		1	MVRD	P	UTU-33433	N2995
BONANZA 1023-4L	04	100S	230E	4304738211	16393		1	GW	P	NWSW		1	MVRD	P	UTU-33433	N2995
BONANZA 1023-4P	04	100S	230E	4304738212	16442		1	GW	P	SESE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-4N	04	100S	230E	4304738303	16395		1	GW	P	SESW		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-4FX (RIGSKID)	04	100S	230E	4304739918	16356		1	GW	P	SENW		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5O	05	100S	230E	4304735438	14297		1	GW	P	SWSE		1	WSMVD	P	U-33433	N2995
BONANZA 1023-5AX (RIGSKID)	05	100S	230E	4304735809	14243		1	GW	P	NENE		1	WSMVD	P	U-33433	N2995
BONANZA 1023-5C	05	100S	230E	4304736176	14729		1	GW	P	NENW		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5G	05	100S	230E	4304736177	14700		1	GW	P	SWNE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5M	05	100S	230E	4304736178	14699		1	GW	P	SWSW		1	WSMVD	P	UTU-73450	N2995
BONANZA 1023-5K	05	100S	230E	4304736741	15922		1	GW	P	NESW		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5B	05	100S	230E	4304737318	16904		1	GW	P	NWNE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5E	05	100S	230E	4304737319	16824		1	GW	P	SWNW		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5H	05	100S	230E	4304737320	16793		1	GW	P	SENE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5N	05	100S	230E	4304737321	16732		1	GW	P	SESW		1	WSMVD	P	UTU-73450	N2995
BONANZA 1023-5L	05	100S	230E	4304737322	16825		1	GW	P	NWSW		1	MVRD	P	UTU-33433	N2995
BONANZA 1023-5J	05	100S	230E	4304737428	17055		1	GW	P	NWSE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5P	05	100S	230E	4304738213	16795		1	GW	P	SESE		1	MVRD	P	UTU-33433	N2995
BONANZA 1023-5N-1	05	100S	230E	4304738911	17060		1	GW	P	SESW		1	WSMVD	P	UTU-73450	N2995
BONANZA 1023-5PS	05	100S	230E	4304750169	17323		1	GW	P	NESE	D	1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-5G2AS	05	100S	230E	4304750486	17459		1	GW	P	SWNE	D	1	MVRD	P	UTU 33433	N2995
BONANZA 1023-5G2CS	05	100S	230E	4304750487	17462		1	GW	P	SWNE	D	1	MVRD	P	UTU 33433	N2995
BONANZA 1023-5G3BS	05	100S	230E	4304750488	17461		1	GW	P	SWNE	D	1	MVRD	P	UTU 33433	N2995
BONANZA 1023-5G3CS	05	100S	230E	4304750489	17460		1	GW	P	SWNE	D	1	MVRD	P	UTU 33433	N2995
BONANZA 1023-5N4AS	05	100S	230E	4304752080	18484		1	GW	DRL	SWSW	D	1	WSMVD	DRL	UTU73450	N2995
BONANZA 1023-8C2DS	05	100S	230E	4304752081	18507		1	GW	DRL	SWSW	D	1	WSMVD	DRL	UTU37355	N2995
BONANZA 6-2	06	100S	230E	4304734843	13796		1	GW	TA	NESW		1	WSMVD	TA	UTU-38419	N2995
BONANZA 1023-6C	06	100S	230E	4304735153	13951		1	GW	P	NENW		1	MVRD	P	U-38419	N2995
BONANZA 1023-6E	06	100S	230E	4304735358	14170		1	GW	P	SWNW		1	MVRD	P	U-38419	N2995
BONANZA 1023-6M	06	100S	230E	4304735359	14233		1	GW	P	SWSW		1	WSMVD	P	U-38419	N2995
BONANZA 1023-6G	06	100S	230E	4304735439	14221		1	GW	P	SWNE		1	WSMVD	P	UTU-38419	N2995
BONANZA 1023-6O	06	100S	230E	4304735630	14425		1	GW	TA	SWSE		1	WSMVD	TA	U-38419	N2995

✱ not moved in unit

BONANZA 1023-6A	06	100S	230E	4304736067	14775		1	GW	P	NENE		1	WSMVD	P	U-33433	N2995
BONANZA 1023-6N	06	100S	230E	4304737211	15672		1	GW	P	SESW		1	WSMVD	P	UTU-38419	N2995
BONANZA 1023-6L	06	100S	230E	4304737212	15673		1	GW	P	NWSW		1	WSMVD	P	UTU-38419	N2995
BONANZA 1023-6J	06	100S	230E	4304737213	15620		1	GW	P	NWSE		1	WSMVD	P	UTU-38419	N2995
BONANZA 1023-6F	06	100S	230E	4304737214	15576		1	GW	TA	SENW		1	WSMVD	TA	UTU-38419	N2995
BONANZA 1023-6P	06	100S	230E	4304737323	16794		1	GW	P	SESE		1	WSMVD	P	UTU-38419	N2995
BONANZA 1023-6H	06	100S	230E	4304737324	16798		1	GW	S	SENE		1	WSMVD	S	UTU-33433	N2995
BONANZA 1023-6D	06	100S	230E	4304737429	17020		1	GW	P	NWNW		1	WSMVD	P	UTU-38419	N2995
BONANZA 1023-6B	06	100S	230E	4304740398	18291		1	GW	P	NWNE		1	WSMVD	P	UTU-33433	N2995
BONANZA 1023-6M1BS	06	100S	230E	4304750452	17578		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6N1AS	06	100S	230E	4304750453	17581		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6N1CS	06	100S	230E	4304750454	17580		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6N4BS	06	100S	230E	4304750455	17579		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6I2S	06	100S	230E	4304750457	17790		1	GW	P	NESE	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6I4S	06	100S	230E	4304750458	17792		1	GW	P	NESE	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6J3S	06	100S	230E	4304750459	17791		1	GW	P	NESE	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6P1S	06	100S	230E	4304750460	17793		1	GW	P	NESE	D	1	WSMVD	P	UTU 38419	N2995
BONANZA 1023-6A2CS	06	100S	230E	4304751430	18292		1	GW	P	NWNE	D	1	WSMVD	P	UTU33433	N2995
BONANZA 1023-6B4BS	06	100S	230E	4304751431	18293		1	GW	P	NWNE	D	1	WSMVD	P	UTU33433	N2995
BONANZA 1023-6B4CS	06	100S	230E	4304751432	18294		1	GW	P	NWNE	D	1	WSMVD	P	UTU33433	N2995
BONANZA 1023-6C4BS	06	100S	230E	4304751449	18318		1	GW	P	NENW	D	1	WSMVD	P	UTU38419	N2995
BONANZA 1023-6D1DS	06	100S	230E	4304751451	18316		1	GW	P	NENW	D	1	WSMVD	P	UTU38419	N2995
FLAT MESA FEDERAL 2-7	07	100S	230E	4304730545	18244		1	GW	S	NENW		1	WSMVD	S	U-38420	N2995
BONANZA 1023-7B	07	100S	230E	4304735172	13943		1	GW	P	NWNE		1	MVRD	P	U-38420	N2995
BONANZA 1023-7L	07	100S	230E	4304735289	14054		1	GW	P	NWSW		1	WSMVD	P	U-38420	N2995
BONANZA 1023-7D	07	100S	230E	4304735393	14171		1	GW	P	NWNW		1	WSMVD	P	U-38420	N2995
BONANZA 1023-7P	07	100S	230E	4304735510	14296		1	GW	P	SESE		1	WSMVD	P	U-38420	N2995
BONANZA 1023-7H	07	100S	230E	4304736742	15921		1	GW	P	SENE		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7NX (RIGSKID)	07	100S	230E	4304736932	15923		1	GW	P	SESW		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7M	07	100S	230E	4304737215	16715		1	GW	P	SWSW		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7K	07	100S	230E	4304737216	16714		1	GW	P	NESW		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7E	07	100S	230E	4304737217	16870		1	GW	P	SWNW		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7G	07	100S	230E	4304737326	16765		1	GW	P	SWNE		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7A	07	100S	230E	4304737327	16796		1	GW	P	NENE		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7O	07	100S	230E	4304738304	16713		1	GW	P	SWSE		1	MVRD	P	UTU-38420	N2995
BONANZA 1023-7B-3	07	100S	230E	4304738912	17016		1	GW	P	NWNE		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-07JT	07	100S	230E	4304739390	16869		1	GW	P	NWSE		1	WSMVD	P	UTU-38420	N2995
BONANZA 1023-7J2AS	07	100S	230E	4304750474	17494		1	GW	P	NWSE	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 1023-7J2DS	07	100S	230E	4304750475	17495		1	GW	P	NWSE	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 1023-7L3DS	07	100S	230E	4304750476	17939		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 1023-7M2AS	07	100S	230E	4304750477	17942		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 1023-7N2AS	07	100S	230E	4304750478	17940		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 1023-7N2DS	07	100S	230E	4304750479	17941		1	GW	P	NWSW	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 1023-7O4S	07	100S	230E	4304750480	17918		1	GW	P	SESE	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 1023-7P2S	07	100S	230E	4304750482	17919		1	GW	P	SESE	D	1	WSMVD	P	UTU 38420	N2995
BONANZA 8-2	08	100S	230E	4304734087	13851		1	GW	P	SESE		1	MVRD	P	U-37355	N2995

BONANZA 8-3	08	100S	230E	4304734770	13843		1	GW	P	NWNW		1	MVRD	P	U-37355	N2995
BONANZA 1023-8A	08	100S	230E	4304735718	14932		1	GW	P	NENE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8L	08	100S	230E	4304735719	14876		1	GW	P	NWSW		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8N	08	100S	230E	4304735720	15104		1	GW	P	SESW		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8F	08	100S	230E	4304735989	14877		1	GW	S	SENW		1	WSMVD	S	UTU-37355	N2995
BONANZA 1023-8I	08	100S	230E	4304738215	16358		1	GW	P	NESE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8K	08	100S	230E	4304738216	16354		1	GW	P	NESW		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8M	08	100S	230E	4304738217	16564		1	GW	P	SWSW		1	MVRD	P	UTU-37355	N2995
BONANZA 1023-8G	08	100S	230E	4304738218	16903		1	GW	P	SWNE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8E	08	100S	230E	4304738219	16397		1	GW	P	SWNW		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8C	08	100S	230E	4304738220	16355		1	GW	P	NENW		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8B	08	100S	230E	4304738221	16292		1	GW	P	NWNE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8H	08	100S	230E	4304738222	16353		1	GW	P	SENE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8O	08	100S	230E	4304738305	16392		1	GW	P	SWSE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8B-4	08	100S	230E	4304738914	17019		1	GW	P	NWNE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-8A1DS	08	100S	230E	4304750481	17518		1	GW	P	NENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8A4BS	08	100S	230E	4304750483	17519		1	GW	P	NENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8B1AS	08	100S	230E	4304750484	17520		1	GW	P	NENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8B2AS	08	100S	230E	4304750485	17521		1	GW	P	NENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8O2S	08	100S	230E	4304750495	17511		1	GW	P	NWSE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8J1S	08	100S	230E	4304750496	17509		1	GW	P	NWSE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8O3S	08	100S	230E	4304750497	17512		1	GW	P	NWSE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8J3	08	100S	230E	4304750498	17510		1	GW	P	NWSE		1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8C4CS	08	100S	230E	4304750499	17544		1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8D2DS	08	100S	230E	4304750500	17546		1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8D3DS	08	100S	230E	4304750501	17545		1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8F3DS	08	100S	230E	4304750502	17543		1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8A4CS	08	100S	230E	4304751131	18169		1	GW	P	NWNE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8B3BS	08	100S	230E	4304751132	18167		1	GW	P	NWNE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8C1AS	08	100S	230E	4304751133	18166		1	GW	P	NWNE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8G3AS	08	100S	230E	4304751134	18168		1	GW	P	NWNE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8E2AS	08	100S	230E	4304751135	18227		1	GW	P	SENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8F3BS	08	100S	230E	4304751136	18227		1	GW	P	SENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8F4AS	08	100S	230E	4304751137	18224		1	GW	P	SENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8F4DS	08	100S	230E	4304751138	18225		1	GW	P	SENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8J2CS	08	100S	230E	4304751139	18226		1	GW	P	SENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8G4DS	08	100S	230E	4304751140	18144		1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8H2DS	08	100S	230E	4304751141	18142		1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8H3DS	08	100S	230E	4304751142	18143		1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8H4DS	08	100S	230E	4304751143	18141		1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8I4BS	08	100S	230E	4304751144	18155		1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8J4BS	08	100S	230E	4304751145	18154		1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8P1AS	08	100S	230E	4304751146	18156		1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8P2BS	08	100S	230E	4304751147	18153		1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8P4AS	08	100S	230E	4304751148	18157		1	GW	P	NESE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8E2DS	08	100S	230E	4304751149	18201		1	GW	P	NWSW	D	1	WSMVD	P	UTU 37355	N2995

BONANZA 1023-8E3DS	08	100S	230E	4304751150	18200		1	GW	P	NWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8K1CS	08	100S	230E	4304751151	18199		1	GW	P	NWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8K4CS	08	100S	230E	4304751152	18198		1	GW	P	NWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8L3DS	08	100S	230E	4304751153	18197		1	GW	P	NWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8M2AS	08	100S	230E	4304751154	18217		1	GW	P	SWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8M2DS	08	100S	230E	4304751155	18216		1	GW	P	SWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8N2BS	08	100S	230E	4304751156	18218		1	GW	P	SWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8O3CS	08	100S	230E	4304751157	18254		1	GW	P	SWSE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8N3DS	08	100S	230E	4304751158	18215		1	GW	P	SWSW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8O4AS	08	100S	230E	4304751159	18252		1	GW	P	SWSE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8P2CS	08	100S	230E	4304751160	18251		1	GW	P	SWSE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-8P3CS	08	100S	230E	4304751161	18253		1	GW	P	SWSE	D	1	WSMVD	P	UTU 37355	N2995
CANYON FEDERAL 2-9	09	100S	230E	4304731504	1468		1	GW	P	NENW		1	MVRD	P	U-37355	N2995
SOUTHMAN CANYON 9-3-M	09	100S	230E	4304732540	11767		1	GW	S	SWSW		1	MVRD	S	UTU-37355	N2995
SOUTHMAN CANYON 9-4-J	09	100S	230E	4304732541	11685		1	GW	S	NWSE		1	MVRD	S	UTU-37355	N2995
BONANZA 9-6	09	100S	230E	4304734771	13852		1	GW	P	NWNE		1	MVRD	P	U-37355	N2995
BONANZA 9-5	09	100S	230E	4304734866	13892		1	GW	P	SESW		1	MVRD	P	U-37355	N2995
BONANZA 1023-9E	09	100S	230E	4304735620	14931		1	GW	P	SWNW		1	WSMVD	P	U-37355	N2995
BONANZA 1023-9I	09	100S	230E	4304738223	16766		1	GW	P	NESE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-9D	09	100S	230E	4304738306	16398		1	GW	P	NWNW		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-9J	09	100S	230E	4304738811	16989		1	GW	P	NWSE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-9B3BS	09	100S	230E	4304750503	17965		1	GW	P	SENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-9B3CS	09	100S	230E	4304750504	17968		1	GW	P	SENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-9H2BS	09	100S	230E	4304750505	17966		1	GW	P	SENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-9H2CS	09	100S	230E	4304750506	17967		1	GW	P	SENE	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 10-2	10	100S	230E	4304734704	13782		1	GW	P	NWNW		1	MVRD	P	U-72028	N2995
BONANZA 1023-10L	10	100S	230E	4304735660	15164		1	GW	P	NWSW		1	WSMVD	P	U-38261	N2995
BONANZA 1023-10E	10	100S	230E	4304738224	16501		1	GW	P	SWNW		1	MVRD	P	UTU-72028	N2995
BONANZA 1023-10C	10	100S	230E	4304738228	16500		1	GW	P	NENW		1	MVRD	P	UTU-72028	N2995
BONANZA 1023-10C-4	10	100S	230E	4304738915	17015		1	GW	P	NENW		1	MVRD	P	UTU-72028	N2995
BONANZA 11-2 ★	11	100S	230E	4304734773	13768		1	GW	P	SWNW		1	MVMCS	P	UTU-38425	N2995
BONANZA 1023-11K	11	100S	230E	4304735631	15132		1	GW	P	NESW		1	WSMVD	P	UTU-38425	N2995
BONANZA 1023-11B	11	100S	230E	4304738230	16764		1	GW	P	NWNE		1	MVRD	P	UTU-38425	N2995
BONANZA 1023-11F	11	100S	230E	4304738232	16797		1	GW	P	SENW		1	MVRD	P	UTU-38425	N2995
BONANZA 1023-11D	11	100S	230E	4304738233	16711		1	GW	P	NWNW		1	MVRD	P	UTU-38425	N2995
BONANZA 1023-11G	11	100S	230E	4304738235	16826		1	GW	P	SWNE		1	MVRD	P	UTU-38425	N2995
BONANZA 1023-11C	11	100S	230E	4304738309	16736		1	GW	P	NENW		1	MVRD	P	UTU-38425	N2995
BONANZA 1023-11J	11	100S	230E	4304738310	16839		1	GW	P	NWSE		1	WSMVD	P	UTU-38424	N2995
BONANZA 1023-11N	11	100S	230E	4304738311	16646		1	GW	P	SESW		1	MVRD	P	UTU-38424	N2995
BONANZA 1023-11M	11	100S	230E	4304738312	16687		1	GW	P	SWSW		1	MVRD	P	UTU-38424	N2995
BONANZA 1023-11L	11	100S	230E	4304738812	16987		1	GW	P	NWSW		1	WSMVD	P	UTU-38424	N2995
NSO FEDERAL 1-12	12	100S	230E	4304730560	1480		1	GW	P	NENW		1	MVRD	P	UTU-38423	N2995
WHITE RIVER 1-14	14	100S	230E	4304730481	1500		1	GW	S	NENW		1	MVRD	S	U-38427	N2995
BONANZA 1023-14D	14	100S	230E	4304737030	16799		1	GW	P	NWNW		1	MVRD	P	UTU-38427	N2995
BONANZA 1023-14C	14	100S	230E	4304738299	16623		1	GW	P	NENW		1	MVRD	P	UTU-38427	N2995
BONANZA FEDERAL 3-15	15	100S	230E	4304731278	8406		1	GW	P	NENW		1	MVRD	P	U-38428	N2995

★ not moved into unit

BONANZA 1023-15H	15	100S	230E	4304738316	16688		1	GW	P	SENE		1	MVRD	P	UTU-38427	N2995
BONANZA 1023-15J	15	100S	230E	4304738817	16988		1	GW	P	NWSE		1	MVRD	P	UTU-38427	N2995
BONANZA 1023-15H4CS	15	100S	230E	4304750741	17492		1	GW	P	NESE	D	1	MVRD	P	UTU 38427	N2995
BONANZA 1023-15I2AS	15	100S	230E	4304750742	17493		1	GW	P	NESE	D	1	WSMVD	P	UTU 38427	N2995
BONANZA 1023-15I4BS	15	100S	230E	4304750743	17490		1	GW	P	NESE	D	1	WSMVD	P	UTU 38427	N2995
BONANZA 1023-15P1BS	15	100S	230E	4304750744	17491		1	GW	P	NESE	D	1	WSMVD	P	UTU 38427	N2995
LOOKOUT POINT STATE 1-16	16	100S	230E	4304730544	1495		3	GW	P	NESE		3	WSMVD	P	ML-22186-A	N2995
BONANZA 1023-16J	16	100S	230E	4304737092	15987		3	GW	OPS	NWSE		3	WSMVD	OPS	ML-22186-A	N2995
BONANZA 1023-17B	17	100S	230E	4304735747	15165		1	GW	P	NWNE		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-17C	17	100S	230E	4304738237	16585		1	GW	P	NENW		1	WSMVD	P	UTU-37355	N2995
BONANZA 1023-17D3S	17	100S	230E	4304750511	17943		1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-17E2S	17	100S	230E	4304750512	17944		1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-17E3AS	17	100S	230E	4304750513	17945		1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-17E3CS	17	100S	230E	4304750514	17946		1	GW	P	NENW	D	1	WSMVD	P	UTU 37355	N2995
BONANZA 1023-18G	18	100S	230E	4304735621	14410		1	GW	P	SWNE		1	WSMVD	P	U-38241	N2995
BONANZA 1023-18B	18	100S	230E	4304735721	14395		1	GW	P	NWNE		1	WSMVD	P	U-38421	N2995
BONANZA 1023-18DX (RIGSKID)	18	100S	230E	4304736218	14668		1	GW	P	NWNW		1	WSMVD	P	U-38241	N2995
BONANZA 1023-18A	18	100S	230E	4304738243	16625		1	GW	P	NENE		1	WSMVD	P	UTU-38421	N2995
BONANZA 1023-18F	18	100S	230E	4304738244	16624		1	GW	P	SENW		1	WSMVD	P	UTU-38421	N2995
BONANZA 1023-18E	18	100S	230E	4304738245	16645		1	GW	P	SWNW		1	MVRD	P	UTU-38421	N2995
BONANZA 1023-18C	18	100S	230E	4304738246	16734		1	GW	P	NENW		1	MVRD	P	UTU-38421	N2995
BONANZA 1023-18G-1	18	100S	230E	4304738916	17135		1	GW	P	SWNE		1	WSMVD	P	UTU-38421	N2995
BONANZA 1023-18D3AS	18	100S	230E	4304750448	17498		1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18D3DS	18	100S	230E	4304750449	17499		1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18E2DS	18	100S	230E	4304750450	17497		1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18E3AS	18	100S	230E	4304750451	17496		1	GW	P	SENW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18L2S	18	100S	230E	4304750520	18111		1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18L3S	18	100S	230E	4304750521	18110		1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18K3AS	18	100S	230E	4304751061	18112		1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18K3BS	18	100S	230E	4304751063	18113		1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18M2AS	18	100S	230E	4304751064	18117		1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18M2DS	18	100S	230E	4304751065	18116		1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18N2AS	18	100S	230E	4304751066	18114		1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-18N2DS	18	100S	230E	4304751067	18115		1	GW	P	SWNW	D	1	WSMVD	P	UTU 38421	N2995
BONANZA 1023-10F	10	100S	230E	4304738225	16565			GW	P	SENW			MVRD	P	UTU 72028	N2995
BONANZA 1023-6D1AS	6	100S	230E	4304751450	18320			GW	P	NENW	D		WSMVD	P	UTU 38419	N2995
BONANZA 1023-6C1CS	6	100S	230E	4304751448	18319			GW		NENW	D				UTU 38419	N2995
BONANZA 1023-6D3AS	6	100S	230E	4304751452	18317			GW	P	NENW	D		WSMVD	P	UTU 38419	N2995